SHEET NO.	REFERENCE NO.	STATION	SIDE	CODE	SIZE (mm)	630														
							REMOVAL OF POLE MOUNTED SIGN AND DISPOSAL	REMOVAL OF POLE MOUNTED SIGN AND STORAGE	REMOVAL OF GROUND MOUNTED SIGN AND DISPOSAL	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	REMOVAL OF GROUND MOUNTED SIGN SUPPORT AND DISPOSAL	REMOVAL OF GROUND MOUNTED SIGN SUPPORT AND STORAGE	SIGN, DOUBLE FACED, STREET NAME	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	SIGN, FLAT SHEET	SIGN, FLAT SHEET, TYPE G	SIGN, EXTRUSHEET	ONE WAY SUPPORT NO. 3 POST	STREET NAME SIGN SUPPORT	GROUND MOUNTED SUPPORT, NO. 2 POST	GROUND MOUNTED SUPPORT, NO. 3 POST
							EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	SQ. METER	SQ. METER	SQ. METER	METER	EACH	METER	METER
206	81	4+315.0	RT.	R-55-300	300 X 450										0.14					3.75	
206	82	4+338.0	RT.	R-10-600	600 X 750		1							1	0.45						
206	83	4+340.0	LT.	R-55-300	300 X 450										0.14						
206	84	4+340.0	LT.	R-10-600	600 X 750				1		1				0.45						4.5
206	85	4+346.3 (NO WORK)	LT.																		
206	86	4+375.0	RT.	R-55-300	300 X 450										0.14					3.75	
206	87	4+385.5	RT.					1													
206	88	4+400.0	LT.	R-55-300	300 X 450										0.14					3.75	
206	89	4+401.0	RT.							1		1									
206	90	4+435.5	RT.	R-55-300	300 X 450									1	0.14						
206	91	4+460.5	LT.	R-55-300	300 X 450									1	0.14						
206	92	4+502.7	RT.	R-55-300	300 X 450									1	0.14						
206	93	4+502.7	RT.				1														
206	94	4+531.0	LT.	R-55-300	300 X 450									1	0.14						
206	95	4+604.0	RT.	R-55-300	300 X 450									1	0.14						
206	96	4+633.5	LT.	R-55-300	300 X 450									1	0.14						
206	97	4+645.8	RT.					1													
206	98	4+675.0	RT.	R-55-300	300 X 450										0.14					3.75	
206	99	4+695.7	RT.				1														
207	100	4+705.0	LT.	R-55-300	300 X 450										0.14					3.75	
207	101	4+744.5	RT.	R-55-300	300 X 450									1	0.14						
207	102	4+762.5	RT.							1		1									
207	103	4+773.6	LT.	R-55-300	300 X 450									1	0.14						
207	104	4+773.6	LT.	R-10-600	600 X 750				1		1			1	0.45						
207	105	4+785.3	LT.	M-40-600	600 X 300				1		1				0.18						4.2
207	106	4+785.3	LT.	M-2-600-3	750 X 600				1						0.45						
207	107	4+789.4	RT.					1													
207	108	4+789.4	RT.						1												
207	109	4+820.0	RT.	R-4L-600	600 X 900				1		1				0.54						4.2
207	110	4+829.1	LT.	R-3L-600	600 X 750										0.45						4.75
207	111	4+829.1	LT.	R-157-600	600 X 750										0.45						
207	112	4+845.5	RT.	R-10-600	600 X 750				1		1				0.45						4.2
207	113	4+845.5	RT.	R-55-300	300 X 450				1						0.14						
207	114	4+853.0	LT.	D-14	VAR X 300				1		1		1						1		
207	115	4+877.5	LT.	R-55-300	300 X 450		1								0.14					3.75	
207	116	4+934.0	RT.	R-55-300	300 X 450		1								0.14					3.75	
207	117	4+947.0	LT.	R-55-300	300 X 450		1								0.14					3.75	
207	118	4+970.0	LT.	W-85-900	900 X 900				1		1				0.81						4.2
207	119	4+975.7	RT.						1		1										
207	120	4+995.0	RT.	R-55-300	300 X 450		1								0.14					3.75	
TOTALS CARRIED TO SHEET 212							7	3	11	2	8	2	1	10	7.34				1	33.75	26.05

CALCULATED

CHECKED

SIGNING SUB-SUMMARY

LAK-640-3.444