	REFERENCE NO.	PLAN & PROFILE SHEET NO.	STATION FROM	STATION TO	SIDE	202 PIPE REMOVED 600 mm AND UNDER	202 MANHOLE REMOVED	202 CATCH BASIN REMOVED	603 150 mm CONDUIT, TYPE F (*)	603 300 mm CONDUIT, TYPE B, AS PER PLAN	603 300 mm CONDUIT, TYPE C, AS PER PLAN	603 375 mm CONDUIT, TYPE B, AS PER PLAN	603 450 mm CONDUIT, TYPE B, AS PER PLAN	603 525 mm CONDUIT, TYPE B, AS PER PLAN	603 600 mm CONDUIT, TYPE B, AS PER PLAN	603 675 mm CONDUIT, TYPE B, AS PER PLAN (62.5 D-LOAD)	604 CATCH BASIN NO. 6 AS PER PLAN	604 CATCH BASIN NO. 3 AS PER PLAN	604 CATCH BASIN NO. 3A AS PER PLAN	604 CATCH BASIN NO. 2-2B AS PER PLAN	604 MANHOLE NO. 3 AS PER PLAN	604 MANHOLE ADJUSTED TO GRADE, AS PER PLAN		605 150 mm SHALLOW PIPE UNDERDRAIN WITH FABRIC WRAP				
						METER	EACH	EACH	METER	METER	METER	METER	METER	METER	METER	METER	EACH	EACH	EACH	EACH	EACH	EACH		METER				
3+500 TO 3+600	D1	69	3+535	3+570.5	R					4.8		35.5									1							
	D2		3+535	3+540	R					5.6									1									
	D3		3+562.5	3+570.5	L&R					22.6							1		1									
	D4		3+570.5	3+596.5	R								26.0								1							
	D5		3+574.5	3+576	R					2.1		2.4						1			1							
	D6		3+576	3+597.75	R							21.8								1								
	D7		3+597.75	3+597.75	R							3.5						1										
	D8		3+597.75	3+599.8	R							6.9			2.4						1							
	D9		3+596.5	3+599.8	L&R							2.2	15.7							1								
	D10		3+596.5	3+600	R										3.5						1							
	R1		3+550.6	3+557.9	R	7.4		1																				
	R2		3+550.7	3+557.9	L&R	18.2		1																				
	R3		3+557.9	3+599.8	R	41.9	1																					
	R4		3+581.7	3+585.7	R	7.6		1																				
	R5		3+597.1	3+599.8	R	7.4																						
	R6		3+596.5	3+599.8	L&R	17.2																						
	U1-U11		3+500	3+600	L&R				27															164.7				
3+600 TO 3+700	D1	70	3+600	3+640	R										40													
	D2		3+640	3+660	R											20					1							
	D3		3+639	3+640	R					2.4	2.4								1									
	D4		3+659.92	3+670.22	L					10.3									2									
	D5		3+659.92	3+700	L&R					21.1						40					1							
	S1		3+664.7		L																	1						
	R1		3+639	3+643.3	R	4.6																						
	U1-U8		3+600	3+700	L&R				12															199.3				
3+700 TO 3+800	D1	71	3+700	3+749.45	R											49.5					1							
	D2		3+723.1	3+726.8	R										2.4	2.4					1							
	D3		3+726.18	3+750.6	L					24.4									1									
	D4		3+754	3+758.0	R					4.0									1									
	D5		3+758.0	3+766.8	L					11.3									1									
	D6		3+766.80	3+768	L						2.1								1		1							
	D7		3+758.0	3+790	R					32									1									
	R1		3+725	3+726.8	R	1.5																						
	R2		3+758	3+767	L	11.5																						
	U1-U9		3+700	3+800	L&R				21															196.1				
TOTALS CARRIED TO SHEET 58A						117.3	1	3	60	140.6	4.5	72.3	41.7	0	48.3	111.9	1	2	10	2	10	1		560.1				

CALCULATED

CHECKED

ESTIMATED QUANTITIES – STA. 3+500 TO 3+800

LAK-640-3.444