

MICROFILMED  
APR 2 1984

# GENERAL SUMMARY

COMPUTED BY: D.A.S. 4/81  
CHECKED BY: G.S. 5/81

FHWA REGION	STATE	PROJECT
5	OHIO	

9  
27

LAKE COUNTY  
LAK-84-1448

ITEM	SHEET NUMBER													ITEM	QUANT	UNIT	DESCRIPTION
	6	11	12	13	14	15	17										
																	ROADWAY
202													3932	202	3932	S.Y.	PAVEMENT REMOVED
202													101	202	101	S.Y.	WEARING COURSE REMOVED
202														202	2	EACH	CATCH BASIN REMOVED
202														202	117	L.F.	PIPE REMOVED 24" AND UNDER
203														203	1974	C.Y.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION
203														203	486	C.Y.	EMBANKMENT
203													5988	203	5988	S.Y.	SUBGRADE COMPACTION
404														404	10	C.Y.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC
410														410	50	C.Y.	TRAFFIC COMPACTED SURFACE, TYPE A OR B
616														616	2	TONS	CALCIUM CHLORIDE
616														616	11	M GALS	WATER
																	PAVEMENT
301													431	301	485	C.Y.S	BITUMINOUS AGGREGATE BASE, AC-20 OR RT-11 OR RT-12
310													969	310	969	C.Y.	SUBBASE, TYPE II
402													244	402	244	C.Y.	ASPHALT CONCRETE, AC-20
404													177	404	177	C.Y.	ASPHALT CONCRETE, AC-20
404														404	12	C.Y.	ASPHALT CONCRETE, AC-20 (DRIVEWAYS)
407													347	407	347	GAL	TACK COAT
407													12	407	12	TONS	COVER AGGREGATE
409													199	409	199	GAL.	SEAL COAT BITUMINOUS MATERIAL
305													3466	305	3466	S.Y.	9" PORTLAND CEMENT CONCRETE BASE
																	DRAINAGE
														603	50	L.F.	6" CONDUIT, TYPE B, AS PER PLAN
														603	50	L.F.	6" CONDUIT, TYPE C, AS PER PLAN
603														603	17	L.F.	6" CONDUIT, TYPE C
603														603	40	L.F.	8" CONDUIT, TYPE D
603														603	202	L.F.	12" CONDUIT, TYPE B
603														603	10	L.F.	12" CONDUIT, TYPE C
603														603	48	L.F.	12" CONDUIT, TYPE D
603														603	58	L.F.	15" CONDUIT, TYPE B
604														604	1	EACH	MANHOLE ADJUSTED TO GRADE (STORM)
604														604	4	EACH	MANHOLE ADJUSTED TO GRADE (SANITARY) (100% LAKE COUNTY FUNDS)
604														604	6	EACH	CATCH BASIN, STANDARD N <sup>o</sup> 2-2-B
604														604	1	EACH	MANHOLE, STANDARD N <sup>o</sup> 1
																	EROSION CONTROL
207														207	700	S.Y.	TEMPORARY SEEDING AND MULCHING
207														207	50	EACH	STRAW OR HAY BALES
659														659	8	M.S.F.	MOWING
659														659	0.04	TON	COMMERCIAL FERTILIZER
659														659	200	S.Y.	REPAIR SEEDING AND MULCHING
659														659	2	M GALS	WATER
659														659	3478	S.Y.	SEEDING AND MULCHING