

MICROFILMED
APR 2 0 1984

GENERAL SUMMARY

COMPUTED BY: D.A.S. 4/81
CHECKED BY: G.S. 5/81

FHWA REGION	STATE	PROJECT
5	OHIO	

10
27

LAKE COUNTY
LAK-84-14.48

ITEM	SHEET NUMBER												ITEM	QUANT.	UNIT	DESCRIPTION	
	11	13	24														
PAVEMENT MARKINGS																	
621														621	0.52	MILES	EDGE LINE
847														847	0.37	MILES	CENTER LINES, 847.10 TYPE A, INLAID AS PER PLAN
847														847	460	L.F.	TRANSVERSE LINES, 847.10 TYPE A, INLAID AS PER PLAN
847														847	345	L.F.	CHANNELIZING LINES, 847.10 TYPE A, INLAID AS PER PLAN
847														847	105	L.F.	STOP LINES, 847.10 TYPE A, INLAID AS PER PLAN
847														847	6	EACH	LANE ARROWS, 847.10 TYPE A, INLAID AS PER PLAN
847														847	5	EACH	WORD "ONLY" ON PAVEMENT 72 INCH, 847.10 TYPE A, INLAID AS PER PLAN
621														621	120	S.F.	ISLAND MARKING
SIGNING																	
630														630	63	S.F.	SIGNS, FLAT SHEET
630														630	49	L.F.	GROUND MOUNTED SUPPORTS N° 2 POST
630														630	15	L.F.	GROUND MOUNTED SUPPORTS N° 3 POST
630														630	63	L.F.	GROUND MOUNTED SUPPORTS N° 4 POST
630														630	13	EACH	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE
630														630	15	EACH	REMOVAL OF GROUND MOUNTED POST SUPPORT
FOR SIGNAL GENERAL SUMMARY SEE SHEET N° 24																	
614														614	LUMP	LUMP	MAINTAINING TRAFFIC
623														623	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES
624														624	LUMP	LUMP	MOBILIZATION, AS PER PLAN