

# GENERAL SUMMARY

CALC. BY: JR DATE: CHKD. BY: JA DATE:	LAK - 84 - 1888	OHIO FHWA REGION 5 PLAN NO. BR-52-86	4 11
--	-----------------	--	---------

SHEET NUMBER		ITEM	QUANT.	UNIT	DESCRIPTION
		201	LUMP	SUM	CLEARING AND GRUBBING
		202	30	L.F.	GUTTER REMOVED
		202	325	L.F.	GUARDRAIL REMOVED
		203	174	C.Y.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION
		606	275	L.F.	GUARDRAIL, TYPE 5
		606	2	EA.	ANCHOR ASSEMBLY, STD. TYPE A
		609	212	L.F.	CURB, STD. TYPE 6, AS PER PLAN
		659	590	S.Y.	SEEDING AND MULCHING
		659	13	M. GAL.	WATER
		603	75	L.F.	12" CONDUIT, TYPE B, AS PER PLAN
		603	34	L.F.	12" CONDUIT, TYPE C
		604	1	EA.	CATCH BASIN, STD. No. 2-2-B
		604	1	EA.	CATCH BASIN, STD. No. 6
		604	1	EA.	MANHOLE, STD. No. 3
		614	.18	MI.	TEMPORARY CENTERLINES, CLASS I
		614	.35	MI.	TEMPORARY EDGELINES, CLASS I
		615	174	S.Y.	TEMPORARY PAVEMENT, CLASS B, AS PER PLAN
		621	.18	MI.	EDGE LINES
		621	.09	MI.	CENTER LINES
		622	180	L.F.	TEMPORARY CONCRETE BARRIER, AS PER PLAN
		614	LUMP	SUM	MAINTAINING TRAFFIC
		623	LUMP	SUM	CONSTRUCTION LAYOUT STAKES
		624	LUMP	SUM	MOBILIZATION
		503	468	C.Y.	UNCLASSIFIED EXCAVATION
		503	LUMP	SUM	COFFERDAMS CRIBS AND SHEETING
		505	LUMP	SUM	PILE DRIVING EQUIPMENT MOBILIZATION
		507	27	EACH	STEEL POINTS
		507	891	L.F.	STEEL PILES HP 10 x 42 (AS PER PLAN)
		509	2826	POUND	REINFORCING STEEL
		511	24	C.Y.	CLASS "C" CONCRETE, DEADMAN ANCHOR (AS PER PLAN)
		518	62	C.Y.	POROUS BACKFILL (AS PER PLAN)
		202	10	L.F.	PIPE REMOVED, OVER 24"
		202	LUMP	SUM	STRUCTURES REMOVED
		SPECIAL	70	L.F.	BULKHEAD, SHEET PILING, WALER AND CAP ASSEMBLY
		SPECIAL	LUMP	SUM	BULKHEAD ANCHORAGE SYSTEM
		SPECIAL	LUMP	SUM	FILTER FABRIC CONCRETE BAG