

CALC BY: JEP 9-84
 CHKD BY: DWL 11-84

SUMMARY OF QUANTITIES

PLAN NO. BR-98-84

PAVEMENT																
REF. NO.	STATION		SIDE	301	310	304	402	404	407	407	408	409	409	608	621	621
	FROM	TO		BITUMINOUS AGGREGATE BASE	SUBBASE TYPE II 6"	AGGREGATE BASE	ASPHALT CONCRETE 1 3/4"	ASPHALT CONCRETE 1 1/4"	TACK COAT	COVER AGGREGATE	BITUMINOUS PRIME COAT	SEAL COAT BITUMINOUS MATERIAL	SEAL COAT COVER AGGREGATE, NO 8	CONCRETE WALK 4"	EDGE LINES WHITE	CENTER LINES DOUBLE YELLOW
				C.Y.	C.Y.	C.Y.	C.Y.	C.Y.	GAL.	TONS	GAL.	GAL.	C.Y.	S.F.	MILES	MILES
1-P	1562+61	1562+71	LT. & RT.	-	-	-	-	.4	2.3	.08	3.6	.36	.1	100	.004	.002
2-P	1562+71	1563+11	LT. & RT.	10.5	17.0	5.6	4.5	3.2			14.2	1.42	.3	400	.016	.008
3-P	1563+11	1563+21	LT. & RT.	-	-	-	-	.4	2.3	.08	3.6	.36	.1	100	.004	.002
TOTALS				10.5	17.0	5.6	4.5	4.0	4.6	.16	21.4	2.14	.5	600	.024	.012

DRAINAGE									
REF. NO.	STATION TO STATION	SIDE	FOR DETAILS SEE SHEET NO.	601	601	602	603	603	603
				RIP RAP USING 6" REINFORCED CONCRETE SLAB	ROCK CHANNEL PROTECTION WITH FILTER TYPE B	CONCRETE MASONRY	CONDUIT, 8" x 59" PIPE-ARCH TYPE A, 707.02	12" CONDUIT, TYPE B, 706.02	8" CONDUIT TYPE B, 706.02
				S.Y.	C.Y.	C.Y.	L.F.	L.F.	L.F.
1-D	1562+91	LT. & RT.		7.2	17	4.3	129		
2-D	1562+71 - 1562+91	LT.	-					20	
3-D	1562+71 - 1562+91	LT.	-						20
4-D	1562+91 - 1563+11	RT.	-						20
TOTALS				7.2	17	4.3	129	20	40


OR TYPE A - 8" x 59" 707.22, OR 53" x 83" 706.04 CLASS HE-III

GUARDRAIL				
REF. NO.	STATION TO STATION	SIDE	202	
			GUARDRAIL REMOVED	
			L.F.	
1-G	1562+17 - 1563+43	LT.	126	
TOTALS			126	

659 SEEDING AND MULCHING			
SEEDING AND MULCHING	SEEDING AND MULCHING	AGRICULTURAL LIMING	COMMERCIAL FERTILIZER
	SQ. YD. x 9	SQ. FT. x 100 / 1000 x 2000	SQ. FT. x 20 / 1000 x 2000
SQ. YD.	SQ. FT.	TONS	TONS
518	4655	.23	.05

ROADWAY								
REF. NO.	STATION TO STATION	SIDE	202	202	202	203	203	203
			STRUCTURE REMOVED	PAVEMENT REMOVED	WALK REMOVED	EXCAVATION	EMBANKMENT	SUBGRADE COMPACTION
			LUMP	SQ. YD.	SQ. FT.	CU. YD.	CU. YD.	SQ. YD.
1-R	1562+86	LT. & RT.	LUMP					
2-R, 3R	1562+71 - 1563+11	LT. & RT.		71	600*			142
	1562+36 - 1563+36	LT. & RT.				2	299	
TOTALS			LUMP	71	600	2	299	142

* INCLUDES FEATHER AREAS STA 1562+61 TO STA 1562+71 & STA 1563+11 TO STA 1563+21



DEBEVEC - SALO & ASSOCIATES, INC.
 CIVIL ENGINEERS SURVEYORS
 PAINESVILLE OHIO

DRAWN BY	DATE
SCALE	CHK'D BY
FILE #	DATE
W. O. #	

S.R. 84 CULVERT REPLACEMENT

SUMMARY OF QUANTITIES

MADISON VILLAGE, OHIO

4. _____

3. _____

2. _____

1. _____

5
11

DRAWING 44-142 35026

DEBEVEC - SALO & ASSOCIATES, INC. CIVIL ENGINEERS SURVEYORS