



Station	Left	Right
160	777.41	
161	777.50	
162	777.53	
163	776.93	
164	776.17	776.36
165	775.42	775.61
166	774.89	775.01
167	774.72	774.53
168	774.53	774.15
169	774.25	773.87
170	773.96	773.58
171	773.77	773.39
172	773.56	773.18
173	773.13	772.91
174	772.45	772.51
175	771.85	772.04
176	771.40	771.59
177	771.16	
178	770.69	
179	770.44	
180	770.19	
181	769.93	
182	769.49	769.68
183	769.47	769.49

ADD.04 TO PROPOSED ELEVATIONS

B.M. Elev. 770.755 x S.E. Cor. W. Walk
Strawberry Lane 51.6' & Sta. 168+54 Resurface New Pavement

FEATHERED AREA-HARMONY LANE
180 Sq.Yds. 1 1/2" Ave. Asph. Conc. Surface Course
15 Sq.Yds. 8" Portland Cement Concrete Base Course
25 Sq.Yds. 4" Subbase
8 Cu.Yds. Excavation
Deduct 175 Lin. Ft. Conc. Curb for Intersection
90 Lin. Ft. Conc. Curb Type 3-B
15 Sq. Yds. Bituminous Tack Coat

FEATHERED AREA-STRAWBERRY LANE
180 Sq.Yds. 1 1/2" Ave. Asph. Conc. Surface Course
15 Sq.Yds. 8" Portland Cement Conc. Base Course
25 Sq.Yds. 4" Subbase
8 Cu.Yds. Excavation
Deduct 175 Lin. Ft. Conc. Curb for Intersection
90 Lin. Ft. Conc. Curb Type 3-B
15 Sq. Yd. Bituminous Tack Coat

Excavation	254	Cu.Yds.
Embankment	305	Cu.Yds.
Emb + 22 %	372	Cu.Yds.

ESTIMATED QUANTITIES

ITEM	STATION TO STATION	5" Crushed 2" Asph. Aggreg. Course	Base Course	Sq.Yds.	Mon. Assembly in Place	Excavation Box	Adjust C.B. to Grade	Abandon C.B.	Build C.B.	Adjust to Grade	Hyd. Valves	Manholes	Hydrants
DRIVES	I-AB to 8-AB			160									
MONUMENT BOXES	I-M				1								
CATCH BASINS							3	1	1				
WATER VALVES										6			
MANHOLES											3	2	3
HYDRANTS & HYD. VALVES													
TOTALS		160	160	31	1	3	1	1	1	6	3	2	3