

# GENERAL SUMMARY

CALCULATED  
 R.I.P.  
 8/95  
 CHECKED  
 D.J.W.  
 8/95

SHEET NUMBER														ITEM	GRAND	UNIT	DESCRIPTION	AS PER PLAN
6	7	9	10	15	16	17	18	32		EXT.	TOTAL			DESIGNATION				
														<b>ROADWAY</b>				
										201	11000	LUMP		CLEARING AND GRUBBING				
										202	11200	LUMP		PORTIONS OF STRUCTURE REMOVED				
				881.0						202	32000	881.0	LIN.FT.	CURB REMOVED				
				47.0						202	35100	47.0	LIN. FT.	PIPE REMOVED, 24" AND UNDER				
				862.50						202	38000	862.50	LIN.FT.	GUARDRAIL REMOVED				
					455	944	268			203	12000	1,667	CU.YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION				
					78	55	15			203	20000	148	CU.YD.	EMBANKMENT				
				862.50						606	13050	862.50	LIN.FT.	GUARDRAIL, TYPE 5A				
				881.0						609	26000	881.0	LIN.FT.	CURB, TYPE 6				
500										616	10000	500	M.GAL.	WATER				
50										616	20000	50	TON	CALCIUM CHLORIDE				
	35									802	00100	35	EACH	BARRIER REFLECTOR, TYPE A				
														<b>EROSION CONTROL</b>				
342										207	10000	342	SQ.YD.	TEMPORARY SEEDING AND MULCHING				
800										207	30000	800	LIN.FT.	FILTER FABRIC FENCE				
50										207	70000	50	EACH	STRAW OR HAY BALES				
					646	876	188			659	10000	1,710	SQ.YD.	SEEDING AND MULCHING				
86.0										659	14000	86.0	SQ.YD.	REPAIR SEEDING AND MULCHING				
0.01				0.15						659	20000	0.16	TON	COMMERCIAL FERTILIZER				
				0.77						659	30000	0.77	TON	AGRICULTURAL LIMING				
2.0				2.0						659	35000	4.0	M-GAL.	WATER				
														<b>DRAINAGE</b>				
				40.0						603	01500	40.0	LIN.FT.	6" CONDUIT, TYPE F, 707.17 NON-PERFORATED, ASTM D-3034 SDR35, SS931 OR SS944				
				47.0						603	06700	47.0	LIN.FT.	15" CONDUIT, TYPE F, 707.05, TYPE C				
				834.0						605	11100	834.0	LIN.FT.	6" SHALLOW PIPE UNDERDRAIN				
														<b>MAINTENANCE OF TRAFFIC</b>				
	5									404	35000	5	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC				
	50									410	12000	50	CU.YD.	TRAFFIC COMPACTED SURFACE, TYPE A OR B				
			108							614	12800	108	EACH	TEMPORARY RAISED PAVEMENT MARKER				
		49								614	13302	49	EACH	BARRIER REFLECTOR, TYPE B2				
		97								614	13350	97	EACH	OBJECT MARKER				
		0.06								614	21000	0.06	MILE	TEMPORARY CENTER LINE, CLASS I				
				0.18						614	22000	0.18	MILE	TEMPORARY EDGE LINE, CLASS I				
		26								614	26000	26	LIN.FT.	TEMPORARY STOP LINE, CLASS I				
	10									616	10000	10	M.GAL.	WATER				
	1									616	20000	1	TON	CALCIUM CHLORIDE				
			970							622	40020	970	LIN.FT.	PORTABLE CONCRETE BARRIER, 32"				
														<b>TRAFFIC</b>				
	0.26									642	00302	0.26	MILE	CENTER LINE, TYPE 2				

GENERAL SUMMARY

LAK - 84 - 5.04

DATE: 10-03-96 - TIME: 09:40 - H:\CT\93119\C40\93119396.DWG