

PLOT SUBMITTED:03-SEP-1999 15:17

2050166A.dgn

2060199A.dgn

PLOTTED BY: calanni

PROJECTS\PI20601\BDGN\20601

SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	5a	6	7	8	9	10	11	12							
											201	11000	LS	LS	CLEARING AND GRUBBING	
					150	125					202	38000	275	LF	GUARDRAIL REMOVED	
	25										203	11001	25	CY	EXCAVATION INCLUDING EMBANKMENT CONSTRUCTION, AS PER PLAN	
				10							203	12000	10	CY	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
				4.1							301	46000	4.1	CY	BITUMINOUS AGGREGATE BASE, PG64-22	9
				4.1							304	20000	4.1	CY	AGGREGATE BASE	9
				2.4							407	10000	2.4	GAL	TACK COAT	9
				1.2							448	46050	1.2	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	9
	5										448	46060	5	CY	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG64-22 (UNDER GUARDRAIL)	
				0.8							448	47020	0.8	CY	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	9
				20							518	21100	20	CY	POROUS BACKFILL	
				10.7							521	15501	10.7	MFBM	BRIDGE TIMBER, AS PER PLAN	8
						10					603	01500	10	LF	6" CONDUIT, TYPE F	
						1					604	36600	1	EA	PRECAST REINFORCED CONCRETE OUTLET	
						110					605	11110	110	LF	6" SHALLOW PIPE UNDERDRAIN WITH FILTER WRAP	
	125										606	13000	125	LF	GUARDRAIL, TYPE 5	9
	150										606	13001	150	LF	GUARDRAIL, TYPE 5, AS PER PLAN	8
											614	11000	LS	LS	MAINTAINING TRAFFIC	
											623	10000	LS	LS	CONSTRUCTION LAYOUT STAKES	
											624	10000	LS	LS	MOBILIZATION	
				2840							863	90000	2840	LB	STRUCTURAL STEEL, MISC.: RETAINING WALL STEEL	

GENERAL SUMMARY

LAK-86-1.71