

I:\PROJECTS\LAK86\dgn\g007.dgn 07-MAY-2002 2:00PM bblayney

SHEET NUMBER				PARTICIPATION				ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4A	4B	9											
											ROADWAY		
		75					202	38000	75	LIN FT	GUARDRAIL REMOVED		
		20					203	20000	20	CU YD	EMBANKMENT		
22							253	01001	22	SO YD	PAVEMENT REPAIR, AS PER PLAN	4A	
		25					606	13001	25	LIN FT	GUARDRAIL, TYPE 5, AS PER PLAN	4A	
		50					606	13050	50	LIN FT	GUARDRAIL, TYPE 5A		
											DRAINAGE		
15							603	01100	15	LIN FT	6" CONDUIT, TYPE C		
											TIEBACK WALL		
		LUMP					503	21300	LUMP		UNCLASSIFIED EXCAVATION		
		159					507	00200	159	LIN FT	STEEL PILES HP12X53, FURNISHED		
		77					507	00250	77	LIN FT	STEEL PILES HP12X53, DRIVEN	4A	
		11					507	93300	11	EACH	STEEL POINT (OR SHOE)		
		25					518	21100	25	CU YD	POROUS BACKFILL		
		4.1					521	15501	4.1	MFBM	BRIDGE TIMBER, AS PER PLAN	4A	
		3268					863	90000	3268	POUND	STRUCTURAL STEEL, MISC.: RETAINING WALL STEEL, HP 12x53 WALER		
		345					863	90000	345	POUND	STRUCTURAL STEEL, MISC.: TIEBARS AND ACCESSORIES	4A	
											MAINTENANCE OF TRAFFIC		
	30						407	10000	30	GALLON	TACK COAT		
	10						448	47010	10	CU YD	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-28		
	10						614	13000	10	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC		
							614	11000	LUMP		MAINTAINING TRAFFIC		
							623	10000	LUMP		CONSTRUCTION LAYOUT STAKES		
							624	10000	LUMP		MOBILIZATION		

GENERAL SUMMARY

LAK-86-1.75