# GENERAL NOTES

## PROJECT DESCRIPTION

THE WORK PROPOSED FOR THIS PROJECT CONSISTS OF APPROXIMATELY 350 FEET OF CELLULAR COFFERDAM RETAINING WALL, AS SHOWN IN THE PLANS; AND REPAIR AND OVERLAY OF THE PAVEMENT FROM FAY RD. TO S.L.M. 2.60.

THE ALIGNMENT AND PROFILE OF THE EXISTING PAVEMENT WILL NOT BE CHANGED.

# UTILITIES OWNERSHIP

LISTED BELOW ARE THE UTILITIES AND OWNERS LOCATED WITHIN THE PROJECT CONSTRUCTION LIMITS. THE OHIO DEPARTMENT OF TRANSPORTATION HAS USED THE BEST AVAILABLE INFORMATION TO DETERMINE THE UTILITY COMPANIES SERVING THIS AREA, BUT CANNOT GUARANTEE THE UTILITY COMPANY LIST IS COMPLETE.

CLEVELAND ELECTRIC ILLUMINATING CO. LAKE CO. DEPT. OF UTILITIES 7755 AUBURN RD. PAINESVILLE, OHIO 44077 ATTN: RICH KERNEY, PHILLIP MULLET (216) 953-7751 (216) 953-7741 FAX 953-7750

EAST OHIO GAS CO. 1201 EAST 55th STREET CLEVELAND, OHIO 44103 ATTN: PAUL ARENDASH (216) 736-6675 FAX 736-6780

*AMERITECH* 13630 LORAIN AVE. - 4th FLOOR CLEVELAND, OHIO 44/// ATTN: SHELLEY ARMSTRONG (216) 476-6142 FAX 476-6/42

CONSUMERS OHIO WATER LAKE ERIE DIVISION 8644 STATION ST., P.O. BOX 960 MENTOR, OHIO 44060-0960 MARK MICKSHAW (440) 255-3421; FAX: 255-6522

LAKE CO. WATER ADMINISTRATION BUILDING 105 MAIN ST. PAINESVILLE, OHIO 44077 ATTN: ALBERT SAARI (440) 664-3247

CITY OF PAINESVILLE P.O. BOX 601 PAINESVILLE, OHIO 44077 ELECTRIC: THOMAS GREEN (440) 352-9301 FAX: 357-1966 WATER: WILLIAM VARGYARS (440) 352-9301 FAX: 639-4998

TCI CABLEVISION OF OHIO INC.. 7757 AUBURN RD. CONCORD, OHIO 44077 (440) 354-8000

# EQUIPMENT AND MATERIAL STORAGE

IN ORDER TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC THE CONTRACTOR'S ATTENTION IS DIRECTED TO 614.03. IN ADDITION THE FOLLOWING PROVISIONS SHALL APPLY:

- I) ANY REMOVED ITEMS SHALL NOT BE STORED ON THE RIGHT OF WAY FOR MORE THAN THIRTY DAYS.
- 2) THE STORAGE OF EQUIPMENT, MATERIALS, AND VEHICLES WITHIN THE HIGHWAY RIGHT OF WAY WILL BE PERMITTED. THE NUMBER OF AREAS AND EXACT LOCATIONS SHALL BE APPROVED BY THE ENGINEER.
- 3) ALL DISTURBED AREAS SHALL BE RETURNED TO THEIR ORIGINAL CONDITION AT NO EXPENSE TO THE STATE.

### CONTINGENCY QUANTITIES:

THE CONTRACTOR SHALL NOT ORDER MATERIAL OR PERFORM WORK FOR THE PLAN ITEMS SET UP TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER.

#### RIGHT OF WAY:

ALL WORK IS TO BE PERFORMED WITHIN THE EXISTING RIGHT OF WAY.

#### FINAL INSPECTION:

WORK WHICH IS UNACCEPTABLE OR BECOMES UNACCEPTABLE PRIOR TO FINAL INSPECTION AS DETERMINED BY THE ENGINEER DUE TO CAUSES SUCH AS. BUT NOT LIMITED TO, IMPROPER PLACEMENT, DELAMINATION AND/OR RAVELING, SHALL BE REPAIRED BY A METHOD SUITABLE TO THE ENGINEER AT THE CONTRACTOR'S EXPENSE.

# COOPERATION BETWEEN CONTRACTORS

THE CONTRACTOR SHALL COOPERATE AND COORDINATE HIS OPERATIONS WITH THE CONTRACTOR'S ON OTHER PROJECTS THAT MAY BE IN FORCE DURING THE LIFE OF THIS CONTRACT. NO WAIVER OF ANY PROVISIONS OF 105.07 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS IS INTENDED.