

PLOTTED BY: jgrmovse
 PLOTTED FROM: users\jgrmovse\p17995\p17995.dgn
 17995GCA.DGN
 PLOT SUBMITTED: 11-NOV-1998 06:59

SHEET NUMBER						PARTICIPATION			ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	7	9	10	11	14									
									201	11000		LUMP	CLEARING AND GRUBBING	4
		31							203	60000	31	STA.	LINEAR GRADING	4
500									251	01000	500	SQ.FT.	PARTIAL DEPTH PAVEMENT REPAIR	4
		383							254	01000	383	SQ.FT.	PAVEMENT PLANING, BITUMINIOUS	
		56							301	46000	56	CU.YD.	BITUMINIOUS AGGREGATE BASE, PG 64-22	
	60	482							407	10000	542	GALLON	TACK COAT	
		241							407	14000	241	GALLON	TACK COAT FOR INTERMEDIATE COURSE	
		89							448	46050	89	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 2, PG 64-22	
		11							448	46060	11	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22, (UNDER GUARDRAIL)	4
	20	158							448	47020	178	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22	
		33035							504	11101	33035	SQ.FT.	STEEL SHEET PILING, LEFT IN PLACE, AS PER PLAN MINIMUM SECTION MODULUS OF 1.9 IN ² /FT. OF WALL	5
		200							507	93300	200	EACH	STEEL POINT (OR SHOE)	
					2				601	32200	2	CU.YD.	ROCK CHANNEL PROTECTION, TYPE C WITH FILTER	
				0.22					602	20000	0.22	CU.YD.	CONCRETE MASONRY	
				74					603	04400	74	LIN.FT.	CONDUIT, 12", TYPE B	
					1				604	04100	1	EACH	CATCH BASIN NO. 2-2A	
				362.5					606	13000	362.5	LIN.FT.	GUARDRAIL, TYPE 5	
				1					606	22010	1	EACH	ANCHOR ASSEMBLY, TYPE E-98	13
				1					606	26500	1	EACH	ANCHOR ASSEMBLY, TYPE T	
	10								614	13000	10	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
	50								616	10000	50	MGAL	WATER	
	2								616	20000	2	TON	CALCIUM CHLORIDE	
	20	53							617	10101	73	CU.YD.	COMPACTED AGGREGATE, TYPE A, AS PER PLAN	4
									642	00102	0.66	MILE	EDGE LINE, TYPE 2 PAINT (WHITE)	
									642	00302	0.33	MILE	CENTER LINE, TYPE 2, PAINT	
		431							659	10000	431	SQ.YD.	SEEDING AND MULCHING	
					30				670	40000	30	SQ.YD.	DITCH EROSION PROTECTION	
									614	11000		LUMP	MAINTAINING TRAFFIC	
									623	10000		LUMP	CONSTRUCTION LAYOUT STAKES	
									624	10000		LUMP	MOBILIZATION	

GENERAL SUMMARY

LAKE COUNTY
LAK-86-2.33