

PLOTTED BY: jgrmovse
PLOTTED FROM: I:\PROJECTS\16982\16982gna.dgn
16982gna.dgn
PLOT SUBMITTED: 02-JUL-1999 10:25

IV. MAINTENANCE OF TRAFFIC MATERIALS

A. SIGNS

SIGN DIMENSIONS AND SPECIFICATIONS, INCLUDING LETTER SIZES SHALL BE AS PROVIDED IN THE "MANUAL", OR IN DESIGN DRAWINGS PROVIDED BY THE DEPARTMENT OF TRANSPORTATION. THE SIGNS SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER PRIOR TO THE START OF THE PROJECT.

B. SIGN SUPPORTS

SIGN SUPPORTS SHALL BE OF SUFFICIENT SIZE AND MASS AS TO FIRMLY SUPPORT THE SIGNS AT THE APPROPRIATE HEIGHT. SUPPORTS SHALL BE AS SHOWN ON THE STANDARD DRAWINGS.

C. CONES

CONES SHALL BE LOCATED AS SHOWN IN THE "MANUAL" AND THE STANDARD DRAWINGS.

V. PAYMENT

PAYMENT FOR PROVIDING, ERECTING, MAINTAINING AND REMOVING TEMPORARY MAINTENANCE OF TRAFFIC CONTROL DEVICES SHALL BE MADE UNDER THE LUMP SUM PRICE BID FOR ITEM 614 - MAINTAINING TRAFFIC.

ITEM 614 - TEMPORARY PAVEMENT MARKINGS

TEMPORARY MARKINGS SHALL BE PLACED AT THE LOCATIONS OF THE PERMANENT MARKINGS AS SHOWN IN THE TRAFFIC CONTROL PLANS.

AFTER THE HEATER RECYCLING PROCESS IS COMPLETED, THE FOLLOWING TEMPORARY MARKINGS SHALL BE USED:

ITEM 614 - TEMPORARY CENTER LINES, CLASS I, 642 PAINT 4.69 MILE
ITEM 614 - TEMPORARY STOP BARS, CLASS I, 642 PAINT 100 FT.
ITEM 614 - TEMPORARY CROSSWALK LINE, CLASS I, 642 PAINT 52 FT.

AFTER THE SURFACE COURSE IS PLACED, THE FOLLOWING TEMPORARY MARKINGS SHALL BE USED:

ITEM 614 - TEMPORARY CENTER LINES, CLASS II, 642 PAINT 4.69 MILE
ITEM 614 - TEMPORARY STOP BARS, CLASS I, 642 PAINT 100 FT.
ITEM 614 - TEMPORARY CROSSWALK LINE, CLASS I, 642 PAINT 52 FT.

ITEM 614 - WORK ZONE MARKING SIGNS

A QUANTITY OF 26 WORK ZONE MARKING SIGNS (13 - "NO EDGE LINES" OW-167-36 AND 13 - "UNMARKED NO PASSING ZONES" OW-168-36) HAS BEEN CARRIED TO THE GENERAL SUMMARY.

THE CONTRACTOR SHALL ERECT THE WORK ZONE MARKING SIGNS AND PROVIDE TEMPORARY PAVEMENT MARKINGS IN ACCORDANCE WITH STANDARD DRAWING MT-99.10M AND AS DIRECTED BY THE ENGINEER.

CALCULATE
KAS
CHECKED
LDH

MAINTENANCE OF TRAFFIC NOTES

LAKE COUNTY
LAK-86-5.52