

PLOT SUBMITTED:02-JUL-1999 12:1

16982GGA.dgn

PLOTTED BY: jgrmovse
PLOTTED FROM: @PROJECTS@P16982@16982GGA.dgn

SHEET NUMBER										ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
4	5	7	8	10	12	14	15	16							
								412.5		202	38000	412.5	LIN.FT.	GUARDRAIL REMOVED	
								8		202	42000	8	EACH	ANCHOR ASSEMBLY REMOVED, TYPE A	
445										202	54101	445	EACH	RAISED PAVEMENT MARKERS REMOVED FOR STORAGE, AS PER PLAN	
						8025									
						48154									
480								8		203	60000	488	STA.	LINEAR GRADING	4
1500										251	01000	1500	SQ.YD.	PARTIAL DEPTH PAVEMENT REPAIR	
										254	01000	230	SQ.YD.	PAVEMENT PLANING, BITUMINOUS	3
						71727				SPECIAL	40465000	71727	SQ.YD.	ASPHALT CONCRETE PAVEMENT SURFACE HEATER RECYCLING	7-8
						7172				SPECIAL	40466000	7172	GALLON	ASPHALT REJUVENATING AGENT	7-8
						7437				407	10000	7437	GALLON	TACK COAT	
						2582				448	47020	2582	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22	
								32		448	46060	32	CU.YD.	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22 (UNDER GUARDRAIL)	
								59		448	48020	59	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22 (DRIVEWAYS)	4
			6							604	39501	6	EACH	MONUMENT ADJUSTED TO GRADE, AS PER PLAN	
	250									SPECIAL	60450000	250	POUND	MISCELLANEOUS METAL	
								650		606	13000	650	LIN.FT.	GUARDRAIL, TYPE 5	5
								8		606	22010	8	EACH	ANCHOR ASSEMBLY, TYPE E-98	13
						26				614	12460	26	EACH	WORK ZONE MARKING SIGN	
	75									614	13000	75	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
						4.69				614	21100	4.69	MILE	TEMPORARY CENTER LINE, CLASS I, 642 PAINT	
						4.69				614	21500	4.69	MILE	TEMPORARY CENTER LINE, CLASS II, 642 PAINT	
						200				614	26200	200	LIN.FT.	TEMPORARY STOP BAR, CLASS I, 642 PAINT	
						104				614	27200	104	LIN.FT.	TEMPORARY CROSSWALK, CLASS I, 642 PAINT	
	185									617	10101	185	CU.YD.	COMPACTED AGGREGATE, TYPE A, AS PER PLAN	5
				445						621	00201	445	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY, AS PER PLAN	9
	10														
								9.38		642	00102	9.38	MILE	EDGE LINE, TYPE 2	
								4.69		642	00302	4.69	MILE	CENTERLINE, TYPE 2	5
								100		644	00500	100	LIN.FT.	STOP LINE	
								52		644	00600	52	LIN.FT.	CROSS WALK LINE	
								2		644	01110	2	EACH	SCHOOL SYMBOL MARKING (96")	
								5339		659	10000	5339	SQ.YD.	SEEDING AND MULCHING	
								1		659	20000	1	TON	COMMERCIAL FERTILIZER	
			4							SPECIAL	69050000	4	EACH	MAILBOX SUPPORT	
										806	16010	6	MNTH	FIELD OFFICE, TYPE B	
										614	11000		LUMP	MAINTAINING TRAFFIC	
										623	10000		LUMP	CONSTRUCTION LAYOUT STAKES	
										624	10000		LUMP	MOBILIZATION	

GENERAL SUMMARY

LAK-86-5.52

17
17