

GENERAL SUMMARY

CALC. BY:	LAKE COUNTY	OHIO	19
DATE:	LAK-90/271-1.88/0.00	FHWA REGION 5	49
CHKD BY:		FEDERAL PROJECT	
DATE:			

4-MAY-1990 10:14
 PLOT SUBMITTED BY: GRMOVSEK
 ZFI:[100,350]LK90GGA.DGN;2

ITEM	SHEET				NUMBER				PART		ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN SHEET REF.	
	9	11	14	15	16	17	18	49	I	II							
202	260	2640									260	2640	202	2900	EACH	RAISED PAVEMENT MARKERS REMOVED FOR STORAGE	
203	20	200									20	200	203	220	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
251								1100	20000	1100	20000	251	21100	SQ.YD.	PARTIAL DEPTH PAVEMENT REPAIR, AS PER PLAN	9	
252	600	6000								600	6000	252	6600	SQ.YD.	FULL DEPTH RIGID PAVEMENT REMOVAL AND FLEXIBLE REPLACEMENT		
252	2500	22500								2500	22500	252	25000	LIN. FT.	FULL DEPTH PAVEMENT SAWING		
254				64850	535963		87116			64850	623079	254	687929	SQ. YD.	PAVEMENT PLANING, BITUMINOUS		
254	600	6000								600	6000	254	6600	SQ. YD.	PATCHING PLANED SURFACES		
301	10	100								10	100	301	110	CU. YD.	BITUMINOUS AGGREGATE BASE, AC-20, AS PER PLAN	9	
304	20	200								20	200	304	220	CU. YD.	AGGREGATE BASE		
404			10	120						10	120	404	130	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC		
407					6485	62308				6485	62308	407	68793	GAL.	TACK COAT		
446				2252	18610		3024			2252	21634	446	23886	CU. YD.	ASPHALT CONCRETE SURFACE COURSE, TYPE I, AC-20, AS PER PLAN	9	
605	300	3000								300	3000	605	3300	LIN. FT.	AGGREGATE DRAINS		
614			9.00	65.00						9.00	65.00	614	74.00	MILES	TEMPORARY LANE LINES, CLASS II		
614			9.00	120.00						9.00	120.00	614	129.00	MILES	TEMPORARY EDGE LINES, CLASS I		
614				2000							2000	614	2000	LIN. FT.	TEMPORARY GORE MARKINGS, CLASS II		
614				170							170	614	170	LIN. FT.	TEMPORARY STOP LINES, CLASS I		
621						1824	1016				2840	621	2840	LIN. FT.	CURB MARKING		
621						1197	1458				2655	621	2655	SQ. FT.	ISLAND MARKING		
847					3.94	40.75	6.72	3.34		3.94	50.81	847	54.75	MILES	EDGE LINES , 947.02		
847					3.94	25.16	3.37			3.94	28.53	847	32.47	MILES	LANE LINES , 947.02		
847						8081	3679	2472			14232	847	14232	LIN. FT.	CHANNELIZING LINES , 947.02		
847						3357					3357	847	3357	LIN. FT.	TRANSVERSE LINES , 947.02		
847							72				72	847	72	LIN. FT.	STOP LINES , 947.02		
847							8				8	847	8	EACH	LANE ARROWS , 947.02		
847							4				4	847	4	EACH	WORD "ONLY" ON PAVEMENT, 72 IN. , 947.02		
SPEC.			20	200							20	200	SPEC.	220	HOURS	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
614												614	LUMP	LUMP	MAINTAINING TRAFFIC		
623												623	LUMP	LUMP	CONSTRUCTION LAYOUT STAKES, AS PER PLAN	9	
624												624	LUMP	LUMP	MOBILIZATION		