

PLOT SUBMITTED: 25-FEB-1999 16:12

19423TGA.DGN

PLOTTED BY: jgrmovse  
 PLOTTED FROM: I:\PROJECTS\PI\19423\19423TGA.DGN

SHEET NUMBER													ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
6	8	10	12	13	15	33												
		2250											202	54101	2250	EACH	RAISED PAVEMENT MARKER REMOVED FOR STORAGE, AS PER PLAN	6
		200											251	01000	200	SQ. YD.	PARTIAL DEPTH PAVEMENT REPAIR	
												20858	254	01000	20858	SQ. YD.	PAVEMENT PLANING, BITUMINOUS	
													407	10000	45852	GALS	TACK COAT	
													448	50001	19089	CU. YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1H, AS PER PLAN	6
													614	11100	80	HOURS	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
													614	20100	27.32	MILE	TEMPORARY LANE LINE, CLASS 1, 642 PAINT	
													614	22100	32.06	MILE	TEMPORARY EDGE LINE, CLASS 1, 642 PAINT	
													614	23200	10988	LIN FT	TEMPORARY CHANNELIZING LINE, CLASS 1, 642 PAINT	
													614	26200	66	LIN FT	TEMPORARY STOP LINE, CLASS 1, 642 PAINT	
		1000											617	10101	1000	CU. YD.	COMPACTED AGGREGATE, TYPE A, AS PER PLAN	6
													621	00200	2280	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY	
													828	10000	32.06	MILE	EDGE LINE	
													828	10100	27.32	MILE	LANE LINE	
													828	10300	10988	LIN.FT.	CHANNELIZING LINE	
													828	10400	66	LIN.FT.	STOP LINE	
													828	10600	3080	LIN.FT.	TRANSVERSE LINE	
													828	20300	9	EACH	LANE ARROW	
													828	20400	6	EACH	WORD "ONLY" ON PAVEMENT, 72"	
													614	11000	LUMP	MAINTAINING TRAFFIC		
													623	10001	LUMP	CONSTRUCTION LAYOUT STAKES, AS PER PLAN	6	
													624	10000	LUMP	MOBILIZATION		
													806	16000	4	MONTHS	FIELD OFFICE, TYPE A	

GENERAL SUMMARY

LAK-90/271-1.88/0.00