GENERAL SUMMARY

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO		

11
306

TYPE CODE 7221

LAKE COUNTY
LAK-1-10.38

ITEM NO.	SHEET NUMBER 789	13	14	15	16	17	19	20	21	23	24	25	26	27	28	29	30	205	206	207	216	217	218	226	229	305	236	272	237	256	238	296	ITEM NO.	QUAN.	UNIT	DESCRIPTIONS
																																				ROADWAY
E-1	866,020																																E-1	866,020	C.Y.	Roadway Excavation, Method B as per plan
E-1	100,749					11,520			11,151					2224				356	1047	1077	948	863	1684	866	1790				3170				E-1	137,445	S.Y.	Compacted Subgrade
E-9	Lump																																E-9	Lump	Lump	Removal of Trees and Stumps, as per plan
E-11	3,674																																E-11	3,674	M-Gal	Water
E-12																				100	66	18	40						87				E-12	311	L.F.	Pipe Removed 15" and Under, as per plan
E-12																						135	219										E-12	354	L.F.	Pipe Removed Over 15", as per plan
I-13						2656			2,531																								I-13	5,187*	S.F.	4" Sidewalks, Concrete
I-15																			624	336		464	760		32								I-15	2,216	L.F.	Guard Rail, Wire Cable Type, 3 Cables
I-15		350.0	1075.0		562.5	1012.5	537.5	862.5		650.0	887.5	162.5	162.5		250.0	1175.0	1500.0																I-15	9187.5	L.F.	Guard Rail, Steel Beam Std. Type (Deep)
I-8																															14	I-8	14	EA.	Center Line Reference Monuments, as per plan.
I-8																															2	I-8	2	EA.	Monument Assemblies, Standard.
L-1	16,586																																L-1	16,586	C.Y.	Topsoil Stockpiled
L-3	42,168																																L-3	42,168	S.Y.	Placing Stockpiled Topsoil, 12" Depth
L-6			10	31	52			17		27	43	36	17	82	60																		L-6	375	Units	Roadside Cleanup
L-9		18,335	30,570	27,833	33,294		36,206	26,826		35,982	31,100	28,742	31,493	28,264	26,790	30,844	26,819	869	4901	2747	1802	3283	6064	2060	4337		167		12746		2620		L-9	454,694	S.Y.	Seeding and Protecting, as per plan
L-9	0.11	1.67	2.77	2.55	3.03	0.03	3.27	2.43	0.01	3.25	2.81	2.64	2.87	2.68	2.45	2.81	2.43	.09	.46	.25	.17	.31	.55	.19	A1		.02		1.15		.24		L-9	41.65	Tons	Commercial Fertilizer (12-12-12)
L-9		1.80	1.39		.06		.80				.39	1.35	1.03																				L-9	6.82	Tons	Agricultural Liming Material for Shale Slopes
M-10	3																																M-10	3	Tons	Calcium Chloride furnished and applied for maintaining traffic.
T-10	150																																T-10	150	C.Y.	Traffic Compacted Surface Course for Maintaining Traffic
SS-18																															24426	SS-18	24,426	L.F.	Fence, Type "D"
SS-18																															3079	SS-18	3,079	L.F.	Park Fence
I-125	0.39																																I-125	0.39	Mile	4" Barrier Lines
I-125	10.16																																I-125	10.16	Miles	Edge Lines, 4"
I-125	1.87																																I-125	1.87	Miles	Lane Lines and Center Lines 6" Wide
I-125	Lump																																I-125	Lump	Lump	Curb and Island Marking
I-127																											130						I-127	130	EA.	Standard Delineators
L-10	1200	274	229	503	177	159	130	281	62	2	449	633	441	1573	458	215	152	92	175	41	104	99	12		271				6				L-10	7738	S.Y.	Sodding, as per plan
L-10						120										111			68			71											L-10	370	S.Y.	Sodding for Special Berm & Slope Protection, as per plan
S-24																									Lump								S-24	Lump	Lump	Removal of 1 Frame Barn Parcel No. 8 LA
S-25								150																							150		S-25	150	L.F.	4" Asbestos Cement Conduit, Sec. M-206.14, as per Plan
L-12																															100		L-12	100	EA.	Vinca Minor · Myrtle 2 Yr.
L-13																															580		L-13	580**	EA.	Cornus Racemosa · Gray Dogwood - 2-3' - B & B 12"
L-14																															1		L-14	1 *	EA.	Aesculus Glabra · Ohio Buckeye - 1½" to 1¾" - B & B 22"
L-14																															21		L-14	21 ‡	EA.	Liquidamber Styraciflua - Sweet Gum - 1½" to 1¾" - B & B 22"
L-17																															Lump		L-17	Lump	Lump	Pruning Existing Trees
Special																															225		Special	225*	L.F.	Drilled Wells
Special																															2		Special	2 *	EA.	Well Shelter
Special																															2		Special	2 *	EA.	Toilet & Storage Building
Special																															28		Special	28 *	EA.	Park Table
Special																															12		Special	12 *	EA.	Charcoal Grill & Serving Table
Special																															2		Special	2 *	EA.	Bulletin Board

‡18 at Normal Participation & 3 at 100% State

Rev. 11-20-61
Rev. 3-1-60

*100% State
**560 at Normal Participation & 20 at 100% State