

614 WORK ZONE PAVEMENT MARKINGS

GENERAL

THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND WHEN NECESSARY, REMOVE WORK ZONE RETROREFLECTIVE PAVEMENT MARKINGS ON EXISTING, RECONSTRUCTED, RESURFACED OR TEMPORARY ROADS WITHIN THE WORK LIMITS, IN ACCORDANCE WITH THE FOLLOWING REQUIREMENTS.

THE MARKINGS SHALL BE EVALUATED BY THE ENGINEER IN ACCORDANCE WITH THE THREE PERFORMANCE PARAMETERS CONTAINED IN SUPPLEMENT 1047. THE MARKINGS SHALL BE REPAIRED OR REPLACED WHEN THE NUMERICAL RATING OF A PARAMETER IS (a) SIX OR LOWER FOR DURABILITY, (b) FOUR OR LOWER FOR VISUAL EFFECTIVENESS AND (c) FOUR OR LOWER FOR NIGHT VISIBILITY. THE CONTRACTOR SHALL REPAIR OR REPLACE UNSATISFACTORY MARKINGS IMMEDIATELY AND AT NO ADDITIONAL COST TO THE STATE.

TEMPORARY PAVEMENT MARKING MATERIALS

UNLESS OTHERWISE INDICATED ON THE PLANS, TEMPORARY PAVEMENT MARKINGS MAY BE EITHER 641.02 PAINT OR 740.05 TYPE B OR TYPE C PREFORMED MATERIAL.

PAINT

PAINTED MARKINGS SHALL BE IN ACCORDANCE WITH 642 EXCEPT THAT (a) PARAGRAPH 641.11 SHALL NOT APPLY, (b) WHERE THE MARKINGS ARE NOT LIABLE TO BE TRACKED, EITHER CONVENTIONAL OR FAST DRY PAINT MAY BE USED FOR 641.02 AND (c) WHEN APPLIED TO NEW ASPHALT PAVEMENT SURFACES PLACED BY THIS PROJECT, THE SPECIFIED APPLICATION RATE SHALL BE AS FOLLOWS:

LITERS PER KILOMETER OF LINE	WIDTH OF LINE (MILLIMETERS)		
	100	200	300
SOLID LINE	56.6	113.3	169.9
3.0 m DASHED LINE	14.2	-	-
1.2 m DASHED LINE	5.7	-	-
DOTTED LINE	19.0	-	-

(d) WHEN APPLIED TO PLANED ASPHALT PAVEMENT SURFACES, THE SPECIFIED APPLICATION RATE SHALL BE AS FOLLOWS:

LITERS PER KILOMETER OF LINE	WIDTH OF LINE (MILLIMETERS)		
	100	200	300
SOLID LINE	67.9	135.9	203.8
3.0 m DASHED LINE	17.0	-	-
1.2 m DASHED LINE	6.8	-	-
DOTTED LINE	22.7	-	-

TYPE B AND TYPE C PREFORMED MATERIAL

PREFORMED MATERIAL SHALL COMPLY WITH 740.05 EXCEPT THAT NO PREFORMED MATERIAL CONTAINING METAL SHALL BE PLACED ON ANY SURFACE UNLESS IT WILL BE REMOVED LATER BY THE CONTRACTOR. TEMPORARY PAVEMENT MARKINGS OF 740.05 PREFORMED MATERIAL SHALL BE REMOVED PRIOR TO PLACEMENT OF 642 OR 644 SURFACE COURSE MARKINGS AT THAT LOCATION. PREFORMED MATERIAL SHALL BE IN ACCORDANCE WITH 644 EXCEPT AS MODIFIED HEREIN.

PLACEMENT

TEMPORARY MARKINGS SHALL BE COMPLETE AND IN PLACE ON ALL PAVEMENT, INCLUDING RAMPS, PRIOR TO EXPOSING IT TO TRAFFIC. WHEN TEMPORARY MARKINGS CONFLICT WITH THE TRAFFIC PATTERN, THEY SHALL BE REMOVED BY THE CONTRACTOR IN ACCORDANCE WITH 641.10.

LINE PLACEMENT TOLERANCE FOR FINAL SURFACES SHALL BE IN ACCORDANCE WITH 641.07. ON SURFACES OTHER THAN THE FINAL, THE TOLERANCE PERMITTED SHALL BE TWICE THAT IN 641.07. LAYOUT AND PREMARKING SHALL BE IN ACCORDANCE WITH 641.06.

TEMPORARY MARKING CLASSES

CLASS I MARKINGS

CLASS I MARKINGS SHALL BE APPLIED TO THE STANDARD DIMENSIONS AS DEFINED IN 642 WITH THE FOLLOWING EXCEPTION:

1. TRANSVERSE LINES SHALL BE 200 mm IN WIDTH.
2. STOP LINES SHALL BE 300 mm IN WIDTH.
3. CROSSWALK LINES SHALL BE 200 mm IN WIDTH.

CLASS II MARKINGS

CLASS II MARKINGS (ABBREVIATED) SHALL BE DEFINED AS FOLLOWS:

CENTER LINES SHALL CONSIST OF SINGLE, YELLOW 100 mm WIDE BY A MINIMUM OF 1.2 m LONG DASHES SPACED AT A MAXIMUM OF 12.0 m INTERVALS.

LANE LINES SHALL CONSIST OF WHITE 100 mm WIDE BY A MINIMUM OF 1.2 m LONG DASHES SPACED AT A MAXIMUM OF 12.0 m INTERVALS.

GORE MARKINGS SHALL BE CONTINUOUS, WHITE 100 mm LINES PLACED AT THE THEORETICAL GORE OF AN EXIT RAMP OR DIVERGING ROADWAYS.

CONFLICTING EXISTING MARKINGS

THE CONTRACTOR SHALL, PRIOR TO PLACING TEMPORARY MARKINGS, REMOVE ALL CONFLICTING EXISTING MARKINGS VISIBLE TO THE TRAVELING PUBLIC DURING DAYLIGHT OR NIGHTTIME HOURS IN ACCORDANCE WITH 641.10. THE COST FOR REMOVAL OF CONFLICTING MARKINGS SHALL BE INCLUDED IN 614 MAINTAINING TRAFFIC UNLESS SPECIFICALLY ITEMIZED.

THE CONTRACTOR SHALL ALSO REMOVE THE PRISMATIC RETRO-REFLECTOR WITHIN ANY RAISED PAVEMENT MARKER (RPM) WHICH IS IN CONFLICT WITH THE TEMPORARY PAVEMENT MARKINGS. WHEN THE TEMPORARY PAVEMENT MARKINGS ARE REMOVED AND THE RPM IS NO LONGER IN CONFLICT, THE CONTRACTOR SHALL THOROUGHLY CLEAN THE RECESSED REFLECTOR ATTACHMENT AREA OF THE CASTING AND INSTALL A NEW PRISMATIC RETRO-REFLECTOR OF THE SAME KIND AND COLOR. THE COST FOR THIS WORK SHALL BE INCIDENTAL TO THE VARIOUS PAY ITEMS.

ALLOWABLE DURATION OF CLASS II CENTER LINES

EXCEPT AS NOTED BELOW, ANYTIME EXISTING PERMANENT NO PASSING ZONE MARKINGS HAVE BEEN REMOVED OR OBLITERATED AS THE RESULT OF A CONSTRUCTION OPERATION (PAVEMENT GRINDING, ASPHALT PAVEMENT OVERLAYS, ETC.) AND THE SECTION OF PAVEMENT CONTINUES TO BE USED BY THE TRAVELING PUBLIC, THE CONTRACTOR MUST WITHIN 3 CALENDAR DAYS PLACE FINAL CENTER LINE MARKINGS AS SPECIFIED BY THE PLAN. EQUIVALENT 614 CLASS I CENTER LINE MARKINGS MAY BE USED IN LIEU OF FINAL MARKINGS. IN THIS EVENT, THE CONTRACTOR SHALL FURNISH ALL LABOR, EQUIPMENT, AND MATERIAL NECESSARY TO PLACE AND MAINTAIN 614 CLASS I MARKINGS AS PART OF THE LUMP SUM BID FOR MAINTAINING TRAFFIC.

IF AFTER THE ORIGINAL MARKINGS ARE REMOVED OR OBLITERATED, THE CONTRACTOR RETURNS TO THE SUBJECT NO PASSING ZONE AND PLACES A PLAN SPECIFIED PAVEMENT COURSE WITHIN THE 3 CALENDAR DAY LIMIT, OR PERFORMS WORK IN PREPARATION FOR A SUBSEQUENT PAVEMENT COURSE, THE CONTRACTOR WILL HAVE TEMPORARILY SATISFIED THE CONDITIONS OF THE PREVIOUS PARAGRAPH. IN THIS EVENT THE 3 CALENDAR DAY LIMIT WILL BEGIN AGAIN.

SECTIONS OF PAVEMENT WHERE PASSING IS PERMITTED IN BOTH DIRECTIONS SHALL BE GOVERNED BY THE 21 DAY LIMIT DESCRIBED BELOW IN THE PARAGRAPH ENTITLED 'ALLOWABLE DURATION OF CLASS II LANE LINES, GORE MARKINGS AND ABSENCE OF EDGE LINES.'

FOR EACH CALENDAR DAY BEYOND 3 DAYS THAT THIS WORK SHALL REMAIN UNCOMPLETED, THE SUM OF \$200 PER CALENDAR DAY WILL BE DEDUCTED FROM ANY MONEY DUE THE CONTRACTOR, NOT AS A PENALTY BUT AS LIQUIDATED DAMAGES.

ALLOWABLE DURATION OF CLASS II LANE LINES AND GORE MARKINGS AND ABSENCE OF EDGE LINES

ANYTIME EXISTING PERMANENT LANE LINES, GORE MARKINGS OR EDGE LINES HAVE BEEN REMOVED OR OBLITERATED AS THE RESULT OF A CONSTRUCTION OPERATION (PAVEMENT GRINDING, ASPHALT PAVEMENT OVERLAYS, PAVEMENT WIDENING, ETC.) AND THE SECTION OF PAVEMENT CONTINUES TO BE USED BY THE TRAVELING PUBLIC, THE CONTRACTOR MUST WITHIN 21 CALENDAR DAYS PLACE FINAL PAVEMENT MARKINGS AS SPECIFIED BY THE PLAN. EQUIVALENT 614 CLASS I MARKINGS MAY BE USED IN LIEU OF FINAL MARKINGS. IN THIS EVENT, THE CONTRACTOR SHALL FURNISH ALL LABOR, EQUIPMENT, AND MATERIAL NECESSARY TO PLACE AND MAINTAIN 614 CLASS I MARKINGS AS PART OF THE LUMP SUM BID FOR 614 MAINTAINING TRAFFIC.

IF, AFTER THE ORIGINAL MARKINGS ARE REMOVED OR OBLITERATED, THE CONTRACTOR RETURNS TO THE SUBJECT SECTION OF PAVEMENT AND PLACES A PLAN SPECIFIED PAVEMENT COURSE WITHIN THE 21 CALENDAR DAY LIMIT, OR PERFORMS SPECIFIED WORK WHICH REQUIRES A LANE CLOSURE, EXCEPT ROUTINE MAINTENANCE REQUIRED BY 614.02, THE CONTRACTOR WILL HAVE TEMPORARILY SATISFIED THE CONDITIONS OF THE PREVIOUS PARAGRAPH. IN THIS EVENT, THE 21 CALENDAR DAY LIMIT WILL BEGIN AGAIN.

FOR EACH CALENDAR DAY BEYOND 21 DAYS THAT THIS WORK SHALL REMAIN UNCOMPLETED, THE SUM OF \$200 PER CALENDAR DAY WILL BE DEDUCTED FROM ANY MONEY DUE THE CONTRACTOR, NOT AS A PENALTY BUT AS LIQUIDATED DAMAGES.

IF A SECTION OF PAVEMENT IS IN A CONTINUOUS PART OF THE PROJECT THEN A NEW 21 DAY LIMIT FOR RENEWED WORK ON A SECTION SHALL APPLY TO ALL SECTIONS IN THAT PART. IF THE PROJECT IS IN PARTS AND THE TRAVELING PUBLIC WOULD NOT DISCERN THE PARTS AS ONE CONTINUOUS PROJECT, THEN A NEW 21 DAY LIMIT IN ONE PART WILL NOT APPLY TO THE OTHER PARTS. THE TWO DIRECTIONAL SIDES OF A FREEWAY SHALL BE TREATED AS SEPARATE PARTS. WORK ON ONE SIDE OF A FREEWAY SHALL NOT CREATE A NEW 21 DAY LIMIT FOR THE OTHER SIDE.

METHOD OF MEASUREMENT

TEMPORARY PAVEMENT MARKINGS WILL BE MEASURED COMPLETE IN PLACE, BY CLASS AND MATERIAL, IN THE UNITS DESIGNATED. LINE QUANTITIES WILL BE THE LENGTH OF THE COMPLETED STRIPE, INCLUDING GAPS, INTERSECTIONS, AND OTHER SECTIONS OF PAVEMENT NOT NORMALLY MARKED.

TEMPORARY PAVEMENT MARKINGS WILL INCLUDE THE LAYOUT, APPLICATION AND REMOVAL OF THE MARKINGS, WHEN REQUIRED.

BASIS OF PAYMENT

PAYMENT FOR ACCEPTED QUANTITIES COMPLETE IN PLACE WILL BE MADE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIALS, LABOR, INCIDENTALS AND EQUIPMENT FOR PLACEMENT, MAINTENANCE AND NECESSARY REMOVAL OF MARKINGS.

ITEM	UNIT	DESCRIPTION
614	KILOMETER	TEMPORARY LANE LINES, CLASS _____, _____
614	KILOMETER	TEMPORARY CENTER LINES, CLASS _____, _____
614	METER	TEMPORARY CHANNELIZING LINES, CLASS I, _____
614	KILOMETER	TEMPORARY EDGE LINES, CLASS I, _____
614	METER	TEMPORARY GORE MARKINGS, CLASS II, _____
614	METER	TEMPORARY STOP LINES, CLASS I, _____
614	METER	TEMPORARY CROSSWALK LINES, CLASS I, _____
614	METER	TEMPORARY DOTTED LINES, CLASS I, _____

* TYPE MATERIAL (642 PAINT, 740.05 TYPE B OR 740.05 TYPE C OR LEFT BLANK TO PERMIT ANY OF THE THREE)

614 WORK ZONE MARKING SIGNS

GENERAL

THE CONTRACTOR SHALL FURNISH, INSTALL, MAINTAIN AND SUBSEQUENTLY REMOVE WORK ZONE MARKING SIGNS (OW-167, R-33 AND R-34) AND THEIR SUPPORTS WITHIN THE WORK LIMITS IN ACCORDANCE WITH THE FOLLOWING REQUIREMENTS.

THE CONTRACTOR SHALL, IN ADVANCE OF ANY SECTION OF ROADWAY LACKING OMUTCD STANDARD EDGE LINE MARKINGS, ERECT A 'NO EDGE LINES' (OW-167-36) SIGN. ON FREEWAYS AND EXPRESSWAYS AN OW-167-48 SIGN SHALL BE USED. THESE SIGNS SHALL BE IN PLACE PRIOR TO EXPOSING THE ROADWAY TO TRAFFIC. THESE SIGNS SHALL ALSO BE ERECTED ON EACH ENTRANCE RAMP, AT INTERSECTIONS OF THROUGH ROADS TO WARN ENTERING OR TURNING TRAFFIC OF THE CONDITIONS AND AT LEAST ONCE EVERY 3.2 km ALONG THE ROADWAY. THESE SIGNS SHALL BE REMOVED WHEN THEY DO NOT APPLY.

THE CONTRACTOR SHALL AT THE BEGINNING OF EACH NO-PASSING ZONE LACKING OMUTCD STANDARD CENTER LINE MARKINGS, ERECT A 'DO NOT PASS' (R-33-30) SIGN AND AT THE END OF EACH NO-PASSING ZONE, ERECT A 'PASS WITH CARE' (R-34-30) SIGN.

MATERIALS

THE CONTRACTOR MAY USE SIGNS AND SUPPORTS IN USED BUT GOOD CONDITION. SIGN FACES SHALL BE REFLECTORIZED WITH TYPE G SHEETING COMPLYING WITH THE REQUIREMENTS OF 730.19. WORK ZONE MARKING SIGNS SHALL BE PROVIDED WITH SUITABLE YIELDING SUPPORTS OF SUFFICIENT STRENGTH AND STABILITY.

METHOD OF MEASUREMENT

WORK ZONE MARKING SIGNS WILL BE MEASURED AS THE NUMBER OF SIGN INSTALLATIONS, INCLUDING THE SIGN, NECESSARY SUPPORTS AND ALL ATTACHMENT HARDWARE. ALL OTHER WORK ZONE SIGNS SHALL BE INCLUDED IN 614 MAINTAINING TRAFFIC UNLESS SEPARATELY ITEMIZED.

BASIS OF PAYMENT

PAYMENT FOR ACCEPTED QUANTITIES, COMPLETE, IN PLACE WILL BE MADE AT THE CONTRACT UNIT PRICE. PAYMENT SHALL BE FULL COMPENSATION FOR ALL MATERIALS, LABOR, INCIDENTALS AND EQUIPMENT FOR PLACEMENT, MAINTENANCE AND REMOVAL OF THE SIGNS.

ITEM	UNIT	DESCRIPTION
614	EACH	WORK ZONE MARKING SIGNS

METRIC	
BUREAU OF DESIGN SERVICES DIVISION OF HIGHWAYS OHIO DEPARTMENT OF TRANSPORTATION	
MAINTENANCE OF TRAFFIC	DATE 01/30/95
WORK ZONE PAVEMENT MARKINGS AND SIGNS	
STANDARD CONSTRUCTION DRAWING	MT-99.10M
APPROVED <i>[Signature]</i> ENGR. OF DESIGN SERVICES	