

GENERAL SUMMARY

ITEM	SHEET NUMBER														ITEM	QUANT.	UNIT	DESCRIPTION
	4A	6	7	8	9	10	12	13	14	15	16	19						
					1						1				SPEC.	2	EACH	GENERAL CONTRACT REST AREA RESERVOIR ASSEMBLY (EXCEPT ELECTRICAL & PLUMBING WORK)
			1					1							SPEC.	2	EACH	MOTORIST SERVICES BUILDING & STORAGE UNIT (EXCEPT ELECTRICAL, PLUMBING, HEATING & VENTILATING WORK)
	2,000					950									SPEC.	2,950	LN.FT.	SNOW FENCE - TREE PROTECTION
											14				SPEC.	14	EACH	LAKE CO. PRECAST CONCRETE MANHOLE
											1				SPEC.	1	EACH	LAKE CO. PRECAST CONCRETE DROP MANHOLE
				7						7					SPEC.	14	EACH	WASTE RECEPTACLE SLEEVE
				5						7					SPEC.	12	EACH	WASTE RECEPTACLE SLAB
											LUMP				SPEC.	LUMP		PIPE TESTING AND FINAL INSPECTION
											LUMP				SPEC.	LUMP		FEE FOR SEWER TAP PERMIT
						2				2					SPEC.	4	EACH	WOOD BENCH
	LUMP						LUMP								201	LUMP		CLEARING AND GRUBBING
	LUMP						LUMP								202	LUMP		STRUCTURES REMOVED
	1						1								202	2	EACH	PRIVY VAULT REMOVED, AS PER PLAN
	3,035						2,625								202	5,660	SQ.FT.	WALK REMOVED
	390						395								202	785	LN.FT.	CURB REMOVED
						LUMP					LUMP				203	LUMP		EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION
						LUMP					LUMP				203	LUMP		EMBANKMENT
			253								165				452	418	SQ.YD.	7" PLAIN PORTLAND CEMENT CONCRETE PAVEMENT, AS PER PLAN
													3,049		603	3,049	LN.FT.	8" CONDUIT, TYPE C, 706.08 EXTRA STRENGTH, WITH 706.12 JOINTS
													404		603	404	LN.FT.	8" CONDUIT, TYPE C, 706.08 EXTRA STRENGTH, WITH 706.12 JOINTS, AS PER PLAN
					330						315				603	645	LN.FT.	6" CONDUIT, TYPE F
											2				608	3	EACH	CURB RAMP, STANDARD TYPE 2, MODIFIED AS PER PLAN
					3,260						3,680				608	6,940	SQ.FT.	4" CONCRETE WALK
					370						380				609	750	LN.FT.	CURB, STANDARD TYPE 6
117															630	117	SQ.FT.	SIGNS, EXTRUSHEET
72															630	72	LN.FT.	GROUND MOUNTED SUPPORTS, W 10 X 11.5'
4.4															630	4.4	CU.YD.	CONCRETE FOR EMBEDDED FOUNDATIONS
4															630	4	EACH	BREAKAWAY BEAM CONNECTIONS
						725					1,850	3,900			659	6,475	SQ.YD.	SEEDING AND MULCHING
						0.07					0.17	0.90			659	1.14	TON	COMMERCIAL FERTILIZER
						210					200	25			660	435	SQ.YD.	SODDING, AS PER PLAN
															SPEC.	10	EACH	CONCRETE SLAB FOR PICNIC TABLE
															SPEC.	32	EACH	PICNIC TABLE
															SPEC.	2	EACH	CHARCOAL GRILL & SERVING TABLE (WITH SLAB)