

SUB - SUMMARY SEWER NOTES

# SANITARY SEWER QUANTITIES

ITEM	QUANTITY	UNIT	DESCRIPTION
603	3049	LIN. FT.	8" CONDUIT, TYPE C, 706.08 EXTRA STRENGTH, WITH 706.12 JOINTS
603	404	LIN. FT.	8" CONDUIT, TYPE C, 706.08 EXTRA STRENGTH, WITH 706.12 JOINTS, AS PER PLAN
SPECIAL	14	EACH	LAKE COUNTY PRECAST CONCRETE MANHOLE
SPECIAL	1	EACH	LAKE COUNTY PRECAST CONCRETE DROP MANHOLE
SPECIAL	LUMP	LUMP	PIPE TESTING AND FINAL INSPECTION
SPECIAL	LUMP	LUMP	FEE FOR SEWER TAP PERMIT
659	3,900	SQ. FT.	SEEDING AND MULCHING
659	0.90	TON	COMMERCIAL FERTILIZER
660	25	SQ. YD.	SODDING, AS PER PLAN

