

IV. MAINTENANCE OF TRAFFIC SYSTEMS

A. WHEN REQUIRED

WHENEVER ANY PART OF THE TRAVELED SURFACE IS BEING WORKED UPON OR IS OTHERWISE NOT SUITABLE FOR SAFE AND CONVENIENT USE BY VEHICLES, TRAFFIC CONTROL DEVICES SUFFICIENT TO PROTECT SUCH AREAS TO ASSURE THE SAFE AND CONVENIENT PASSAGE OF VEHICULAR TRAFFIC SHALL BE INSTALLED AND MAINTAINED. SUCH TRAFFIC CONTROL DEVICES AND THE MANNER IN WHICH THEY ARE USED SHALL BE CONSISTENT WITH THESE PLANS AND THE OHIO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, HERINAFTER REFERED TO AS THE "MANUAL". THE TRAFFIC CONTROL DEVICE SYSTEM SHALL CONSTITUTE THE MINIMUM PROVISIONS FOR TRAFFIC CONTROL FOR EACH PARTICULAR SITUATION. WHENEVER THE ENGINEER DEEMS IT NECESSARY ESPECIALLY WHERE A GRADE, CURVE, OR MERGE CONDITIONS EXISTS, HE MAY DIRECT THAT ADDITIONAL OR ALTERNATIVE DEVICES BE USED.

B. CONDITIONS

DURING ALL PARTS OF THIS PROJECT, FLAGGERS, SIGNING, BARRICADES, FLASHING ARROWS, ETC. SHALL BE LOCATED AS INDICATED IN THE MANUAL OR AS SHOWN IN THE STANDARD DRAWINGS. TWO-WAY TRAFFIC SHALL BE MAINTAINED ON ONE LANE AT LEAST 10' WIDE AT ALL TIMES.

C. ADVANCE WARNING SIGNS

ALL ADVANCE WARNING SIGNS FOR ANY CONDITION WHICH RESTRICTS TRAFFIC SHALL BE ERECTED BEFORE ANY SUCH RESTRICTION IS PUT INTO EFFECT. ALL SUCH SIGNS SHALL BE COVERED OR REMOVED FROM THE VIEW OF TRAFFIC WHENEVER THEY ARE NOT APPLICABLE.

D. FLAGGERS

AT LEAST TWO FLAGGERS ARE REQUIRED FOR EACH CLOSURE, THE CONTRACTOR SHALL FURNISH ADDITIONAL FLAGGERS AS DIRECTED BY THE ENGINEER.

E. PROTECTION OF PUBLIC

PERSONAL CARS SHALL NOT BE PARKED WITHIN THE R/W.

F. FAILURE TO COMPLY

IF THERE IS ANY FAILURE TO COMPLY WITH PROVISIONS FOR TRAFFIC CONTROL SET OUT IN THESE PLANS AND NOTES, OR WITH THE PROVISIONS OF THE "MANUAL", THE HIGHWAY IN THE VICINITY OF THE WORK AREA SHALL NOT BE CONSIDERED IN A CONDITION FOR THE SAFE AND CONVENIENT USE BY THE TRAVELING PUBLIC. ANY FAILURE TO KEEP THE HIGHWAY, IN THE VICINITY OF THE WORK AREA, IN A CONDITION FOR THE SAFE AND CONVENIENT USE BY THE TRAVELING PUBLIC SHALL BE CONSIDERED A BREACH OF THIS CONTRACT. WORK SHALL BE SUSPENDED UNTIL THE CONTRACTOR COMPLIES WITH THE PROVISIONS OF THE AFOREMENTIONED ITEMS.

ITEM 614 - TEMPORARY PAVEMENT MARKINGS

TEMPORARY MARKINGS SHALL BE PLACED AT THE LOCATIONS OF THE PERMANENT MARKINGS.

AFTER THE PAVEMENT PLANING PROCESS IS COMPLETED, THE FOLLOWING TEMPORARY MARKINGS SHALL BE USED:

- ITEM 614-TEMPORARY EDGE LINE(WHITE), CLASS I, 642 PAINT0.20 MILE
- ITEM 614-TEMPORARY EDGE LINE(YELLOW), CLASS I, 642 PAINT...12.56 MILE
- ITEM 614-TEMPORARY LANE LINE, CLASS I, 642 PAINT.....12.56 MILE

AFTER THE SURFACE COURSE IS PLACED, THE FOLLOWING TEMPORARY MARKINGS SHALL BE USED:

- ITEM 614-TEMPORARY LANE LINE, CLASS II, 642 PAINT.....12.56 MILE

ITEM 614 - BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC

A QUANTITY OF ITEM 614 - BITUMINOUS CONCRETE HAS BEEN PROVIDED TO PROTECT THE TRAFFIC FROM OBSTRUCTIONS INCLUDING, BUT NOT LIMITED TO; POTHOLES, AND TO MAINTAIN TRAFFIC OVER RUTS AND LOW AREAS WHICH ARE LEFT EXPOSED DUE TO PAVEMENT PLANING OPERATIONS. THE FOLLOWING CONTINGENCY QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY:

- ITEM 614 - BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC 30 CU.YD.

I:\PROJECTS\PI\22610\22610GNA.DGN 14-AUG-2001 9:36AM jgrmovse

CALCULATED
KAS
CHECKED
LDH

MAINTENANCE OF TRAFFIC NOTES

LAKE COUNTY
LAK-90-12.40