

I:\PROJECTS\1422610\2261099a.dgn 14-AUG-2001 9:40AM jgr movse

SHEET NUMBER										ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.	CALCULATED KAS	CHECKED LDH
4	6	7	8	10													
										202	54101	1382	EACH	RAISED PAVEMENT MARKER REMOVED FOR STORAGE, AS PER PLAN			
				88421						254	01001	88421	SQ.YD.	PAVEMENT PLANING, BITUMINOUS, AS PER PLAN			
				8843						407	10000	8843	GALLON	TACK COAT			
				3686						448	50001	3686	CU.YD.	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1H, AS PER PLAN			
	30									614	13000	30	CU.YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC			
	25.12									614	20100	25.12	MILE	TEMPORARY LANE LINE, CLASS I, 642 PAINT			
	12.56									614	22100	12.56	MILE	TEMPORARY EDGE LINE, CLASS I, 642 PAINT			
	12.56									614	20500	12.56	MILE	TEMPORARY LANE LINE, CLASS II, 642 PAINT			
		1382								621	00200	1382	EACH	RAISED PAVEMENT MARKER, INSTALLATION ONLY			
				12.56						828	10000	12.56	MILE	EDGELINE			
				12.56						828	10100	12.56	MILE	LANE LINE			
										614	11000		LUMP	MAINTAINING TRAFFIC			
										623	10000		LUMP	CONSTRUCTION LAYOUT STAKES			
										624	10000		LUMP	MOBILIZATION			
										806	16000	3	MONTHS	FIELD OFFICE, TYPE A			

GENERAL SUMMARY

LAK-090-12.40

