

COMPUTATIONS AND SUB-SUMMARIES

LAKE COUNTY
LAK-90-13.00



STATIONS				SIDE	LOCATION	WIDTH OF FEATHER & REMOVAL LIN. FT.	LENGTH OF FEATHER LIN. FT.	LENGTH OF REMOVAL FOR FEATHER LIN. FT.	LENGTH OF APPROACH SLAB LIN. FT.	202 WEARING COURSE REMOVED SQ. YDS.
FEATHER		REMOVAL								
BEGIN	END	BEGIN	END							
279 + 89.00	280 + 89.00	279 + 89.00	280 + 26.50	EB	BEGIN PROJECT	39.0	100.0	37.5		162.5
314 + 73.58	316 + 86.08	314 + 98.58	317 + 11.08	EB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
318 + 97.44	321 + 9.94	318 + 72.44	320 + 84.94	EB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
376 + 92.50	379 + 5.00	377 + 17.50	379 + 30.00	EB	BRIDGE APPROACH	45.0	212.5	187.5	25.0	1062.5
381 + 10.00	383 + 22.50	380 + 85.00	382 + 97.50	EB	BRIDGE LEAVE	44.0	212.5	187.5	25.0	1038.9
457 + 90.25	460 + 2.75	458 + 15.25	460 + 27.75	EB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
463 + 97.25	466 + 9.75	463 + 72.25	465 + 84.75	EB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
649 + 20.12	651 + 32.62	649 + 45.12	651 + 57.62	EB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
656 + 81.08	658 + 93.58	656 + 56.08	658 + 68.58	EB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
705 + 48.66	707 + 61.16	705 + 73.66	707 + 86.16	EB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
709 + 49.04	711 + 61.54	709 + 24.04	711 + 36.54	EB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
730 + 0.00	731 + 37.50	731 + 0.00	731 + 37.50	EB	END PROJECT	39.0	137.5	37.5		162.5
SUBTOTAL ITEM 202 - WEARING COURSE REMOVED - MAINLINE EASTBOUND										9793.1
279 + 89.00	280 + 89.00	279 + 89.00	280 + 26.50	WB	BEGIN PROJECT	39.0	100.0	37.5		162.5
316 + 33.36	318 + 45.86	316 + 58.36	318 + 70.86	WB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
320 + 33.22	322 + 45.72	320 + 8.22	322 + 20.72	WB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
377 + 57.50	379 + 70.00	377 + 82.50	379 + 95.00	WB	BRIDGE APPROACH	62.5	212.5	187.5	25.0	1475.7
381 + 80.00	383 + 92.50	381 + 55.00	383 + 67.50	WB	BRIDGE LEAVE	51.0	212.5	187.5	25.0	1204.2
457 + 90.25	460 + 2.75	458 + 15.25	460 + 27.75	WB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
463 + 97.25	466 + 9.75	463 + 72.25	465 + 84.75	WB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
648 + 58.91	650 + 71.41	648 + 83.91	650 + 96.41	WB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
656 + 12.43	658 + 24.93	655 + 87.43	657 + 99.93	WB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
705 + 61.07	707 + 73.57	705 + 86.07	707 + 98.57	WB	BRIDGE APPROACH	39.0	212.5	187.5	25.0	920.8
709 + 36.63	711 + 49.13	709 + 11.63	711 + 24.13	WB	BRIDGE LEAVE	39.0	212.5	187.5	25.0	920.8
730 + 0.00	731 + 37.50	731 + 0.00	731 + 37.50	WB	END PROJECT	39.0	137.5	37.5		162.5
SUBTOTAL ITEM 202 - WEARING COURSE REMOVED - MAINLINE WESTBOUND										10371.5