

ITEM	10	11	36	38	40	41	58	60	61	62	75	76	77	83	ITEM	GRAND TOTAL	UNIT	DESCRIPTION
																		ROADWAY
201											LUMP				201	LUMP		CLEARING AND GRUBBING
202							242								202	242	SQ. YD.	CONCRETE MEDIAN PAVEMENT REMOVED
202											LUMP			LUMP	202	LUMP		STRUCTURES REMOVED
202											4				202	4	LIN. FT.	PIPE REMOVED, OVER 24"
202			32439												202	32439	LIN. FT.	GUARDRAIL REMOVED, AS PER PLAN
202			800												202	800	LIN. FT.	BARRIER GUARDRAIL REMOVED
202				21131		4117									202	25248	SQ. YD.	WEARING COURSE REMOVED
202	1400														202	1400	EACH	RAISED PAVEMENT MARKERS REMOVED FOR STORAGE
202												4			202	4	LIN. FT.	PIPE REMOVED, 24" & UNDER
202						6600									202	6600	SQ. YD.	PAVEMENT REMOVED
202									2122						202	2122	LIN. FT.	CURB REMOVED, AS PER PLAN
202									LUMP						202	LUMP		PORTIONS OF STRUCTURE REMOVED
202													9		202	9	LIN. FT.	GUTTER REMOVED
202												1			202	1	EACH	CATCH BASIN REMOVED
203						15148		900		144	12				203	16204	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION
203						1842					1014				203	2856	CU. YD.	EMBANKMENT, AS PER PLAN
203				304						12					203	316	STA.	LINEAR GRADING
203		3000													203	3000	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION, AS PER PLAN
404	100														404	100	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC
606			27787.5												606	27787.5	LIN. FT.	GUARDRAIL, TYPE 5
606			600												606	600	LIN. FT.	GUARDRAIL, BARRIER DESIGN, TYPE 5
606			44												606	44	EACH	ANCHOR ASSEMBLY, STANDARD TYPE A
606			9												606	9	EACH	ANCHOR ASSEMBLY, STANDARD TYPE A, BARRIER DESIGN