

TRAFFIC CONTROL QUANTITIES

LAKE COUNTY
LAK-90-13.00 96
120

630 GROUND MOUNTED SIGN SUPPORTS

REF. NO.	STATION	SIDE	CODE	SIZE	FLAT SHEET TYPE G	EXTRU SHEET TYPE G	OVERLAY EXTRU SHEET TYPE G	NO.3 POST	NO.4 POST	S4x77 BEAM	W6x9 BEAM	"ONE-WAY" SUPPORTS, NO.4 POST	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	CONCRETE FOR EMBEDDED FOUNDATION	BREAKAWAY BEAM CONNECTION	REMOVAL OF GROUND MOUNTED SIGN	REMOVAL OF GROUND MOUNTED MAJOR SIGN	REMOVAL OF GROUND MOUNTED BEAM SUPPORT	REMOVAL OF GROUND MOUNTED POST SUPPORT
				INCHES	SQ. FT.	SQ. FT.	SQ. FT.	L.F.	L.F.	L.F.	L.F.	L.F.	EACH	CU. YDS.	EACH	EACH	EACH	EACH	EACH
122	697+09	WB	N-41	12x48	4.0			13.5											
123	707+29	EB(R)	X-6R	12x36	3.0											1			
124	707+40	EB(L)	X-6L	12x36	3.0											1			
125	709+56	WB(L)	X-6L	12x36	3.0											1			
126	709+64	WB(R)	X-6R	12x36	3.0											1			
S.R. 44 INTERCHANGE																			
I-90																			
127	359+67	WB	W-49R-48	48x48	16.0				17.0-17.0							1		1	
128			EDUC. PLAQUE	EXISTING												1			
* 129	SEE SHEET NO. 103																		
130	369+15	EB	W-SPEC-48	48x48	16.0								1			1			
131			W-143-24	24x24	4.0								1			1			
132	373+00	EB	GF	96x60		40.0					17.0-17.0			0.66	2		1	2	
133	376+48	WB	GF	96x60		40.0					17.0-17.0			0.66	2		1	2	
134	376+83	WB	W-47-48	48x48	16.0				17.0-17.0							1		1	
135	378+28	EB	W-49R-48	48x48	16.0				16.0-16.0							1		1	
S.R. 44																			
136	92+00	NB	I-17-24	24x12	2.0														
137			M-5-24-2	24x24	4.0											1			
138	102+00	NB	M-52B	120x48		40.0				15.0-16.0				0.54	2		1	2	
139	114+00	NB	D-4B	132x72		66.0											1		
140	SEE SHEET NO. 103																		
141	SEE SHEET NO. 103																		
142	118+40	SB	IM-39-24	24x12	2.0											1			
143			M-5-24-2	24x24	4.0											1			
* 144			IM-24-21	21x15	2.2											1			
145	SEE SHEET NO. 103																		
SUBTOTALS					98.2	186.0		13.5	100.0	31.0	68.0		2	1.86	6	14	4	9	

* FOR ADDITIONAL SIGNS SEE SHEET 102