

# TRAFFIC CONTROL QUANTITIES

LAKE COUNTY  
LAK-90-13.00 97  
120

## 630 GROUND MOUNTED SIGN SUPPORTS

REF. NO.	STATION	SIDE	CODE	SIZE	FLAT SHEET	EXTRU SHEET	OVERLAY	FLAT SHEET	NO.3 POST	NO.4 POST	W8x18 BEAM	"ONE-WAY" SUPPORTS, NO.4 POST	SIGN SUPPORT ASSEMBLY, POLE MOUNTED	CONCRETE FOR EMBEDDED FOUNDATION	BREAKAWAY BEAM CONNECTION	REMOVAL OF GROUND MOUNTED SIGN	REMOVAL OF GROUND MOUNTED MAJOR SIGN	REMOVAL OF GROUND MOUNTED BEAM SUPPORT	REMOVAL OF GROUND MOUNTED POST SUPPORT			
					TYPE G	TYPE G	EXTRU SHEET TYPE G	TYPE G AS PER PLAN												SQ. FT.	SQ. FT.	SQ. FT.
S.R. 44 (CONT.)																						
146	SEE SHEET NO. 103																					
147	126+62	SB(R)	X-6R	36x12	3.0					11.5												
148		SB(L)	X-6L	36x12	3.0					11.5												
149	129+15	NB	IM-40-24	24x12	2.0											1						
150			M-5-24-2	24x24	4.0					13.5-13.5						1			1			
151			IM-24-21	21x15	2.2											1						
152	SEE SHEET NO. 103																					
153	140+00	SB	D-4B	132x72		66.0											1					
154	148+00	SB	M-52B	120x48			40.0															
155	156+00	SB	IM-17-24	24x12	2.0																	
* 156			M-5-24-2	24x24	4.0					15.5-15.5						1			2			
RAMP A																						
* 157	13+10	RT	EXISTING	36x36												1			2			
158	13+90	RT	EXISTING	36x12												1			1			
159	14+10	LT	R-2-48	48x48x48	6.9											1						
160		RT	R-2-48	48x48x48	6.9					14.0-14.0						1			1			
RAMP B																						
161	2+70	RT	M-2-24-2	24x24	4.0											1						
162			M-25-21	21x15	2.2											1						
163			D-4B	120x72		60.0											1					
164			SPECIAL	132x36		33.0										1						
165			R-41A-36	36x24	6.0											1						
166	2+70	LT	R-41A-36	36x24	6.0					13.5-13.5						1			1			
167	1+20	RT	SPECIAL	156x24		26.0										1						
168			N-29-24	24x24	4.0											1						
169			N-15-24	24x6	1.0																	
SUBTOTALS					57.2	185.0	40.0		136.0							15	2		8			

\* FOR ADDITIONAL SIGNS SEE SHEET 102

TRAFFIC CONTROL SUB-SUMMARY