SHEET NUMBER								PARTICIPATION			ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
			3		6		10									
															ROADWAY	
			20								202	98100	20	EACH	REMOVAL MISC.: SCRAP TIRES	
			70								202	98500	70	CU YD	REMOVAL MISC.: CONSTRUCTION DEBRIS	
							852				203	11000	852	CU YD	EXCAVATION INCLUDING EMBANKMENT CONSTRUCTION	
							235				203	20000	235	CU YD	EMBANKMENT	
							17								EROSION CONTROL	
											601	34000	17	CU YD	ROCK CHANNEL PROTECTION, TYPE A WITHOUT FILTER	
							1020				659	10000	1020	SQ YD	SEEDING AND MULCHING	
					125						667	10000	125	SQ YD	SEEDING AND JUTE MATTING	
							2203				659	35000	2203	M GAL	WATER	
															DRAINAGE	
					0.69						602	20000	0.69	CU YD	CONCRETE MASONRY	
					26						603	09100	26	LIN FT	21" CONDUIT, TYPE C	
					8						603	13600	8	LIN FT	30" CONDUIT, TYPE C	
					76						603	14200	76	LIN FT	30" CONDUIT, TYPE F	
					52						603	16600	52	LIN FT	36" CONDUIT, TYPE C	
					1						604	01600	1	EACH	CATCH BASIN, NO. 5	
					2						604	31500	2	EACH	MANHOLE, NO. 3	
															MAINTAINING TRAFFIC	
			10								614	12460	10	EACH	WORK ZONE MARKING SIGN	
			10								614	13000	10	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
			10								616	10000	10	M GAL	WATER	
			1								616	20000	1	TON	CALCIUM CHLORIDE	
											614	11000		LUMP	MAINTAINING TRAFFIC	
											623	10000		LUMP	CONSTRUCTION LAYOUT STAKES	
											624	10000		LUMP	MOBILIZATION	

CALCULATED

CHECKED

GENERAL SUMMARY

LAK-90-15.13

PLOTTED BY: dlastovk
PLOTTED FROM: C:\projects\pid19440\dgn\pid19440gga.dgn
PLOT SUBMITTED: 19-FEB-1999 15:47
filename.dgn