

GENERAL SUMMARY

* CONTINGENCY QUANTITY

** CONTAINS CONTINGENCY QUANTITY

SHEET	9	12	15	16		ITEM	ITEM EXTENSION	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
DRAINAGE (CONTD.)											
605	200*					605	13402	200*	LIN.FT.	6" UNCLASSIFIED PIPE UNDERDRAIN FOR SPRINGS	
605			3,700			605	31051	3,700	LIN.FT.	PREFABRICATED EDGE DRAIN, AS PER PLAN	9
605	100*					605	32200	100*	LIN.FT.	AGGREGATE DRAIN FOR SPRINGS	
609				765		609	26000	765	LIN. FT.	CURB, TYPE 6	
PAVEMENT											
252				795		252	01500	795	LIN.FT.	FULL DEPTH PAVEMENT SAWING	
408				119		408	10000	119	GALLON	BITUMINOUS PRIME COAT	
448				25		448	47081	25	CU. YD.	ASPHALT CONCRETE SURFACE COURSE, UNDER GUARDRAIL, TYPE 1, PG 64-22, AS PER PLAN	7,8
MAINTENANCE OF TRAFFIC											
622		3,400 **				622	40020	3,400 **	LIN.FT.	PORTABLE CONCRETE BARRIER, 32"	
626				9		626	00100	9	EACH	BARRIER REFLECTOR, TYPE A	
626		70				626	00200	70	EACH	BARRIER REFLECTOR, TYPE B	
630				1		630	85101	1	EACH	REMOVAL OF GROUND MOUNTED SIGN AND REERECTION, AS PER PLAN	8
614						614	11000	LUMP		MAINTAINING TRAFFIC	
623						623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
624						624	10000	LUMP		MOBILIZATION	

PLOTTED BY: dstupkov
 PLOTTED FROM: I:\users\dstupkov\design\drainage\1\90-1786\plot1.dgn
 90178699.dgn
 PLOT SUBMITTED: 08-JAN-1998 14:25

DESIGNED
 CHECKED
 LDH

GENERAL SUMMARY

LAK-90-17.86