

SUPERELEVATION TABLE

FED. RD. DIVISION	STATE	PROJECT	
2	OHIO	ACI-1103 (28)	



LAKE COUNTY  
LAK-1-20.03

PAINE ROAD

STATION	LT. EDGE	PROFILE	RT. EDGE
25 +50	786.43	786.57	786.43
+75	783.87	784.01	783.87
26 +00	789.05	789.12	788.98
+25	791.66	791.67	791.53
+50	794.26	794.15	794.04
+75	796.80	796.56	796.36
27 +00	799.17	798.87	798.57
+25	801.41	801.11	800.81
+50	803.57	803.27	802.97
+75	805.65	805.35	805.05
28 +00	807.64	807.34	807.04
+25	809.56	809.26	808.96
+50	811.41	811.11	810.81
+75	813.16	812.86	812.56
29 +00	814.85	814.55	814.25
+25	816.33	816.15	815.97
+50	817.72	817.66	817.52
+75	819.07	819.10	818.96
30 +00	820.43	820.53	820.39
+25	821.82	821.96	821.82
+50	823.24	823.38	823.24

RELOC. TRASK - CHADWICK ROAD

STATION	LT. EDGE	PROFILE	RT. EDGE
51 +57.95	853.88	854.28	854.68
51 +75	853.78	854.01	854.24
52 +00	853.63	853.62	853.61
52 +25	853.47	853.32	853.17
52 +50	853.48	853.18	852.88
52 +75	853.60	853.23	852.86
53 +00	853.81	853.44	853.07
53 +25	854.19	853.83	853.47
53 +50	854.60	854.38	854.16
53 +75	855.20	855.12	854.98
54 +00	855.99	856.02	855.88
54 +25	856.92	857.01	856.87
54 +44.71	857.62	857.76	857.62
55 +84.63	861.54	861.68	861.54
56 +00	861.81	861.95	861.85
56 +25	862.19	862.33	862.29
56 +50	862.50	862.64	862.69
56 +75	862.66	862.86	863.06
57 +00	862.67	863.01	863.35
57 +25	862.59	863.07	863.55
57 +50	862.43	863.05	863.67
57 +75	862.20	862.95	863.70
58 +00	862.02	862.77	863.52
58 +25	861.76	862.51	863.26
58 +50	861.42	862.17	862.92
58 +75	861.04	861.79	862.54
59 +00	860.75	861.42	862.09
59 +25	860.51	861.04	861.57
59 +50	860.27	860.66	861.05
59 +75	860.04	860.28	860.52
60 +00	859.76	859.90	860.00
60 +25	859.38	859.52	859.50
60 +50	859.00	859.14	859.06
60 +73.85	858.64	858.78	858.64
102 +70.85	841.19	841.33	841.19
102 +75	841.04	841.18	841.05
103 +00	840.13	840.27	840.20
103 +25	839.14	839.28	839.28
103 +50	838.08	838.22	838.35
103 +75	836.80	837.08	837.36
104 +00	835.46	835.88	836.30
104 +25	834.08	834.64	835.20
104 +50	832.70	833.40	834.10
104 +75	831.41	832.16	832.91
105 +00	830.18	830.93	831.68
105 +25	828.94	829.69	830.44
105 +50	827.70	828.45	829.20
105 +75	826.46	827.21	827.96
106 +00	825.22	825.97	826.72
106 +25	824.06	824.81	825.56
106 +50	823.06	823.81	824.56
106 +75	822.24	822.97	823.70
107 +00	821.70	822.29	822.88
107 +25	821.24	821.69	822.14
107 +50	820.80	821.10	821.40
107 +75	820.34	820.50	820.66
108 +00	819.76	819.90	819.92
108 +25	819.16	819.30	819.24
108 +50	818.56	818.70	818.58
108 +58.89	818.35	818.49	818.35