


GENERAL NOTES

LAKE COUNTY
LAK-90-21.51



GENERAL

FIELD OFFICE

THE CONTRACTOR SHALL PROVIDE A SUITABLE FIELD OFFICE HAVING A MINIMUM OF 800 SQ. FT. OF FLOOR SPACE. PAYMENT SHALL BE AT THE LUMP SUM PRICE BID FOR ITEM 619 FIELD OFFICE.

CONTINGENCY QUANTITIES

THE CONTRACTOR SHALL NOT ORDER MATERIALS OR PERFORM WORK LISTED IN THE GENERAL SUMMARY FOR ITEMS DESIGNATED BY PLAN NOTE TO BE USED "AS DIRECTED BY THE ENGINEER" UNLESS AUTHORIZED BY THE ENGINEER. THE ACTUAL WORK LOCATIONS AND QUANTITIES USED AT THE ENGINEERS DISCRETION SHALL BE MADE A MATTER OF RECORD BY INCORPORATION INTO THE FINAL CHANGE ORDER GOVERNING COMPLETION OF THIS PROJECT.

RIGHT OF WAY

ALL WORK SHALL BE PERFORMED WITHIN THE EXISTING RIGHT OF WAY OR EASEMENTS.

EXISTING TYPICAL SECTIONS

EXISTING TYPICAL SECTIONS HAVE BEEN TAKEN FROM THE RECORDS AND ARE BELIEVED TO REPRESENT THE EXISTING PAVEMENT, BUT THE STATE OF OHIO DOES NOT GUARANTEE THE ACCURACY OF THE SAME.

FOR FURTHER INFORMATION IN REGARD TO THE EXISTING TYPICAL SECTIONS, THE CONTRACTOR SHALL REFER TO THE PREVIOUS CONSTRUCTION PLANS. THESE PLANS MAY BE REVIEWED AT THE OHIO DEPARTMENT OF TRANSPORTATION, DISTRICT TWELVE OFFICES, 10100 BROADWAY AVENUE, GARFIELD HEIGHTS, OHIO 44125.

COOPERATION BETWEEN CONTRACTORS

THE CONTRACTOR SHALL COOPERATE AND COORDINATE HIS OPERATIONS WITH THE CONTRACTORS ON THE OTHER PROJECTS THAT MAY BE IN FORCE DURING THE LIFE OF THIS PROJECT. NO WAIVER OF ANY PROVISIONS OF 105.07 OF THE CONSTRUCTION AND MATERIAL SPECIFICATIONS IS INTENDED.

ALTERNATE METHODS

IF THE CONTRACTOR SO ELECTS, HE MAY SUBMIT ALTERNATE METHODS FOR THE MAINTENANCE OF TRAFFIC, PROVIDED THE INTENT SHOWN IN THE PLANS IS FOLLOWED AND NO ADDITIONAL INCONVENIENCE TO THE TRAVELING PUBLIC RESULTS THEREFROM. NO ALTERNATE PLAN SHALL BE PLACED INTO EFFECT UNTIL APPROVAL HAS BEEN GRANTED, IN WRITING, BY THE DIRECTOR.

EQUIPMENT AND MATERIAL STORAGE

IN ORDER TO PROVIDE FOR THE SAFETY OF THE TRAVELING PUBLIC THE CONTRACTORS ATTENTION IS DIRECTED TO 614.03. IN ADDITION THE FOLLOWING PROVISIONS SHALL APPLY:

1. STORED OR PARKED VEHICLES, MATERIALS AND EQUIPMENT SHALL BE LOCATED BEHIND EXISTING PERMANENT GUARDRAIL OR NOT LESS THAN 30 FEET BEYOND THE TRAVELED WAY.

2. ANY REMOVED ITEMS SHALL NOT BE STORED ON THE RIGHT OF WAY FOR MORE THAN THIRTY DAYS.

3. THE STORAGE OF EQUIPMENTS, MATERIALS AND VEHICLES WITHIN THE HIGHWAY RIGHT OF WAY WILL BE PERMITTED. THE NUMBERS OF AREAS AND EXACT LOCATIONS SHALL BE AS APPROVED BY THE ENGINEER.

4. ALL DISTURBED AREAS SHALL BE RETURNED TO THEIR ORIGINAL CONDITION AT NO EXPENSE TO THE STATE.

WATERING PERMANENT SEEDED AREAS

THE FOLLOWING ESTIMATED QUANTITY IS TO BE USED AS DIRECTED BY THE ENGINEER TO PROMOTE GROWTH FOR THE PERMANENT SEEDED AREAS, AS PER 659.09:

659 WATER _____ 30 M GAL.

ITEM 623 - CONSTRUCTION LAYOUT STAKES, AS PER PLAN

THE CONTRACTOR, IN ADDITION TO THE REQUIREMENTS IN "CONSTRUCTION & MATERIAL SPECIFICATIONS", SHALL STAKE STATION NUMBERS AT THE OUTER EDGES OF THE ROADWAY AND CLOSE TO THE RAMP BASE LINES. THE COMPLETE STATION NUMBERS ARE TO BE MARKED AT ONE HUNDRED-FOOT INTERVALS. PAYMENT FOR FURNISHING, PLACING, AND MAINTAINING CONSTRUCTION LAYOUT STAKES SHALL BE AT THE LUMP SUM PRICE BID FOR ITEM 623 CONSTRUCTION LAYOUT STAKES, AS PER PLAN. EXISTING MONUMENTS ARE SHOWN ON PLAN SHEET 33 TO BE USED AS REFERENCES TO LOCATE THE STATION NUMBERS. RAMP TO MAINLINE STATION EQUATIONS ARE SHOWN ON SHEETS 37 AND 38.

UNDERGROUND UTILITIES

THE LOCATIONS OF THE UNDERGROUND UTILITIES SHOWN ON THE PLANS ARE AS OBTAINED FROM THE OWNERS OF THE UTILITY AS REQUIRED BY SECTION 153.64 OF THE OHIO REVISED CODE.

UTILITY OWNERSHIPS

THE FOLLOWING UTILITIES OWNERS ARE LOCATED WITHIN THE WORK LIMITS OF THE PROJECT:

O.D.O.T.
10100 BROADWAY AVE.
GARFIELD HEIGHTS, OHIO 44125
641-1926

Participation