

PLOTTED BY: ullman
 PLOTTED FROM: c:\dgn\bridges\chome\lak90234.dgn
 filename.dgn
 PLOT SUBMITTED: 26-JUL-1994 13:09

ESTIMATED QUANTITIES								
ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	SUPERSTRUCTURE		GENERAL	
					EB	WB	EB	WB
202	11200	LUMP		PORTIONS OF STRUCTURE REMOVED.	LUMP	LUMP		
513	16001	325	LBS.	STRUCTURAL STEEL FOR REHABILITATION, AS PER PLAN		325		
513	16800	150	EACH	STRUCTURAL STEEL, MISC.: REPLACE RIVET OR BOLT WITH NEW HIGH STRENGTH BOLT	50	100		
513	16800	50	EACH	STRUCTURAL STEEL, MISC.: TIGHTENING LOOSE BOLT	25	25		
513	16800	11	EACH	STRUCTURAL STEEL, MISC.: DRILLING STRUCTURAL STEEL	5	6		
513	16800	1	EACH	STRUCTURAL STEEL, MISC.: TRUSS CHORD REPAIR		1		
SPECIAL	51400100	LUMP		SURFACE PREPARATION OF EXISTING STEEL, SYSTEM OZEU Δ	LUMP	LUMP		
SPECIAL	51400200	LUMP		FIELD PAINTING OF EXISTING STEEL, PRIME COAT, SYSTEM OZEU Δ	LUMP	LUMP		
SPECIAL	51400300	LUMP		FIELD PAINTING OF EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU Δ	LUMP	LUMP		
SPECIAL	51400400	LUMP		FIELD PAINTING OF EXISTING STEEL, FINISH COAT, SYSTEM OZEU Δ	LUMP	LUMP		
SPECIAL	51400504	40	MANHOUR	GRINDING FINS, TEARS, SLIVERS Δ			10	10
SPECIAL	51400504	83180	LIN.FT.	PACK RUST REPAIR AND CAULKING	41090	41090	500	500
SPECIAL	51400504	16	EACH	REMOVAL OF PACK RUST BETWEEN MEMBERS	8	8		
SPECIAL	53000400	12	EACH	STRUCTURAL STEEL MISC.: PENCIL ABRASIVE BLASTING, GRINDING AND NDT	5	7		
SPECIAL		LUMP		CLEANING BRIDGE DECK & DRAINAGE SYSTEMS			LUMP	LUMP
614	11000	LUMP		MAINTAINING TRAFFIC				
619	15010	LUMP		FIELD OFFICE, TYPE B				
624	10000	LUMP		MOBILIZATION				

ΔSEE PROPOSAL NOTE

OHIO DEPARTMENT OF TRANSPORTATION DISTRICT 12 BRIDGE DEPT.	DATE 6/24/94	REVIEWED GWM	DRAWN ABP
	STRUCTURE FILE NUMBER 4304950	REVISER MPC	CHECKED DWL
ESTIMATED QUANTITIES LAK-90-2342 L&R I-90 OVER THE GRAND RIVER			
LAKE COUNTY LAK-90-23.42			