ITEM	EXTENSION	QUANTITY	UNIT	DESCRIPTION
201	11000	LUMP		CLEARING AND GRUBBING
203	20000	100	CUBIC YARD	* EMBANKMENT
601	21100	1040	SQUARE YARD	SLOPE PROTECTION, MISC.: FABRIC FILTER
601	27000	64	CUBIC YARD	DUMPED ROCK FILL, TYPE C
659	10000	2706	SQUARE YARD	SEEDING AND MULCHING
659	20000	0.25	TON	* COMMERCIAL FERTILIZER
659	35000	1	M GALLON	* WATER
838	20751	260	CUBIC YARD	GABIONS WITH ADDITIONAL COATING, AS PER PLAN, ANCHORED
614	11000	LUMP		MAINTAINING TRAFFIC
623	10000	LUMP		CONSTRUCTION LAYOUT STAKES
624	10000	LUMP		MOBILIZATION

* AS DIRECTED BY THE ENGINEER.

DESIGN AGENCY: DISTRICT TWELVE PRODUCTION DEPARTMENT

DESIGNED NRC | DRAWN NRC | REVIEWED JJL | DATE 2/99

CHECKED MJM | REVISED | STRUCTURE FILE NUMBER

ESTIMATED QUANTITIES

LAK-90-23.42

3/7

PLOTTED BY: nconley
PLOTTED FROM: i:\projects\pid17507\equan.dgn
PLOT SUBMITTED: 24-FEB-1999 10:16
equan.dgn