



REF. NO.	STATION		SIDE	DESCRIPTION	UNIT	QUANTITY	TOTALS CARRIED TO GENERAL SUMMARY														
	FROM	TO																			
1BR	3+804	3+857	LT.	REMOVAL OF GROUND MOUNTED POST SUPPORT AND DISPOSAL	EACH	4	4														
2BR	3+804	3+858	RT.	REMOVAL OF GROUND MOUNTED SIGN AND STORAGE	EACH	4															
1-D	3+837.5	3+862.9	LT.	PRESSURE RELIEF JOINT, TYPE D	METER	16.7	30														
2-D	3+860.375	3+862.825	LT.			12.2															
3-D	3+860.375	3+862.430	LT.	BARRIER REFLECTOR TYPE B	EACH	6	12														
4-D	3+862.430	3+862.90	LT.																		
5-D	3+841.05	3+861.6	RT.	GUARDRAIL, TYPE 5	METER	9.525	26.67														
6-D	3+861.233	3+863.288	RT.			7.62															
7-D	3+861.233	3+863.683	RT.	BRIDGE TERMINAL ASSEMBLY TYPE 1	EACH	1	2														
8-D	3+863.288	3+861.6	RT.																		
9-D	3+851.8	3+885	RT.	150 mm UNCLASSIFIED PIPE UNDERDRAIN	METER	1.0	2.0														
10-D	3+882.7	3+883.9	RT.			1.0															
1-GR	3+858.510	3+868.035	LT.	PRECAST REINFORCED CONCRETE OUTLET	EACH	1	1														
2-GR	3+858.510	3+868.035	LT.																		
3-GR	3+859.398	3+867.018	RT.	MANHOLE, NO. 3	EACH	1	2														
4-GR	3+857	3+857	LT.																		
1-RCP	3+841.3	3+850.4	LT.	CATCH BASIN, NO.	3A EACH	6	6														
2-RCP	3+841.8	3+851.2	RT.																		
TOTALS						51.84	36.58	44.32	36.58	51.84	6	6	52	37	45	0.34	0.4	362.3	151.0	211.3	363

STATION	TO	FROM	DESCRIPTION	UNIT	QUANTITY
268	265.284 S.B.	265.243 N.B.	BRIDGE LIMITS = 96.999 (NORTHBOUND)		
267	264.688 S.B.	264.647 N.B.	BRIDGE LIMITS = 95.004 (SOUTHBOUND)		
266	264.092 S.B.	264.051 N.B.	EXC. 121 m <sup>3</sup> EMB. 8 m <sup>3</sup> SEEDING 915 m <sup>2</sup>		
265	263.472 S.B.	263.431 N.B.	TOP 152 mm WATER EL. 258.17±		
264	262.883 S.B.	262.889 N.B.	GROUT-FILLED FABRIC MATS	SC. METER	151.0
263	262.206 S.B.	262.206 N.B.	CONCRETE MASONRY	CU. METER	0.34
262	261.550 S.B.	261.550 N.B.	SLOPE PROTECTION MISC. GROUT-FILLED FABRIC MATS	SC. METER	362.3
261	260.860 S.B.	260.860 N.B.	ROCK CHANNEL PROTECTION, TYPE C, WITH FILTER	CU. METER	0.51
TOTALS CARRIED TO GENERAL SUMMARY					35