

All costs of testing as outlined above will be paid for under the lump sum bid price for High Performance Concrete Testing.

**844.12 METHOD OF MEASUREMENT.** The volume will be measured as per 842.18. The area of high performance concrete will be based on plan dimensions. The above items will include all labor, material, equipment and incidentals necessary to complete these items of work. The above items will also include all costs associated with sealing joints and cracks and sawing grooves into the deck.

Payment for high performance concrete testing will not be made until the Office of Structural Engineering has received the results of all tests.

**844.13 BASIS OF PAYMENT.** Payment for the above completed and accepted quantities will be made at the contract bid price for:

Item	Units	Description
844	Cubic yard (cubic meter)	High performance concrete superstructure (deck)
844	Square yard (square meter)	High performance concrete superstructure (deck)
844	Cubic yard (cubic meter)	High performance concrete superstructure (parapet)
844	Cubic yard (cubic meter)	High performance concrete substructure
844	Lump sum	High performance concrete trial mix
844	Lump sum	High performance concrete testing