

TEMPORARY PAVEMENT MARKINGS

PHASE NO.	STATION		SIDE	614		
				TEMPORARY CENTER LINE, CLASS I, 740.06 TYPE I	TEMPORARY EDGE LINE, CLASS I, 740.06 TYPE I (WHITE)	TEMPORARY STOP LINE, CLASS I, 740.06 TYPE I
	FROM	TO		MILE	MILE	LIN. FT.
I&II	23+00	24+50	CL	0.028		
I&II	24+50	-	RT			14
I	26+00	27+00	RT		0.019	
I&II	35+00	-	LT			14
I&II	35+00	36+50	CL	0.028		
II	32+80	33+80	LT		0.019	
I&II	RAMP I					28
I&II	RAMP K					28
			TOTAL	0.056	0.038	84

TEMPORARY PAVEMENT

PHASE NO.	STATION		SIDE	WIDTH	615
	FROM	TO			TEMPORARY PAVEMENT CLASS B
					SQ YD
I	27+50	28+05*	LT	10'-0"	61.1
I	31+33*	32+00	LT	10'-0"	74.4
			TOTAL		135.5

PORTABLE CONCRETE BARRIER

PHASE NO.	STATION		SIDE	622		614	
	FROM	TO		PORTABLE CONCRETE BARRIER, 32"	PORTABLE CONCRETE BARRIER, 32", BRIDGE MOUNTED, AS PER PLAN	BARRIER REFLECTOR TYPE B2	OBJECT MARKER
				LIN FT	LIN FT	EACH	EACH
I	26+00	28+20	RT	220		15	18
I	28+20	31+30	RT		310	13	26
I	31+30	33+30	RT	200		8	16
II	26+50	28+20	LT	170		7	14
II	28+20	31+30	LT		310	13	26
II	31+30	33+80	LT	250		17	22
	I-90			1760		36	72
			TOTAL	2600	620	109	194

DELINEATION OF GUARDRAIL

PHASE NO.	STATION		SIDE	614
	FROM	TO		BARRIER REFLECTOR TYPE A2
	FROM	TO		EACH
I	25+70	28+10	LT	6
I	31+30	33+60	LT	6
II	26+00	28+20	RT	6
II	31+50	33+80	RT	6
			TOTAL	24

MAINTENANCE OF TRAFFIC SUMMARY

ESTIMATED QUANTITIES

SHEET NUMBER									ITEM	ITEM EXT.	TOTAL	UNIT	DESCRIPTION	FOR AS PER PLAN REFERENCE SEE SHEET
6	7	9	11	12	13	14	15							
									614	11100	100	HR	LAW ENFORCEMENT OFFICER WITH PATROL CAR	
				120					SPECIAL 614	12200	120	LIN FT	TEMPORARY GUARDRAIL	
							275		614	12800	275	EACH	TEMPORARY RAISED PAVEMENT MARKER	
									614	13000	50	CU YD	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC	
									614	13202	24	EACH	BARRIER REFLECTOR, TYPE A2	
									614	13302	109	EACH	BARRIER REFLECTOR, TYPE B2	
									614	13350	194	EACH	OBJECT MARKER	
									614	21200	0.06	MILE	TEMPORARY CENTERLINE, CLASS I, 740.06, TYPE I	
									614	22200	0.04	MILE	TEMPORARY EDGE LINE, CLASS I, 740.06, TYPE I	
									614	26400	84	LIN FT	TEMPORARY STOP LINE, CLASS I, 740.06, TYPE I	
									615	25000	136	SQ YD	TEMPORARY PAVEMENT, CLASS B	
									616	10000	50	M GAL	WATER	
									616	20000	5	TON	CALCIUM CHLORIDE	
									622	40020	2600	LIN FT	PORTABLE CONCRETE BARRIER, 32"	
									622	40041	620	LIN FT	PORTABLE CONCRETE BARRIER, 32", BRIDGE MOUNTED, AS PER PLAN	7
						2			630	85600	2	EACH	REMOVAL OF GROUND MOUNTED MAJOR SIGN AND REELECTION	
						380			642	30000	380	LIN FT	REMOVAL OF PAVEMENT MARKING	

MAINTENANCE OF TRAFFIC QUANTITIES

LAK-90-26.87

File Name: AK\VOL1\0007\0890\STRUCT\12035454
Plot: Scale: 1/4"
Drawn By: Date: 04-12-96 16:48