

0290S033.DGN

SHEET NUMBER										ITEM	ITEM EXTENSION	GRAND TOTAL	UNIT	DESCRIPTION	REMARK
4	5	17	18	19	20										
										ROADWAY					
LUMP										201	11000	LUMP		CLEARING AND GRUBBING	
					178					202	22900	178	SQ YD	APPROACH SLAB REMOVED	
					845					202	38000	845	LIN FT	GUARDRAIL REMOVED	
400										202	38200	400	LIN FT	GUARDRAIL REMOVED FOR REUSE	
										203	12000	1587	CU YD	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
				606	981					203	20000	1253	CU YD	EMBANKMENT	
				332	921					203	21001	195	CU YD	EMBANKMENT USING GRANULAR MATERIAL, AS PER PLAN	SEE SHEET 4
				97.5	97.5										
										203	50000	1826	SQ YD	SUBGRADE COMPACTION	
12										203	60000	12	STATION	LINEAR GRADING	
										606	13000	900	LIN FT	GUARDRAIL, TYPE 5	
400					900					606	16500	400	LIN FT	GUARDRAIL REBUILT, TYPE 5	
										606	26000	4	EACH	ANCHOR ASSEMBLY, TYPE B	
					4					606	35000	4	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE I	
										EROSION CONTROL					
										207	10000	658	SQ YD	TEMPORARY SEEDING AND MULCHING	
										207	30000	200	LIN FT	FILTER FABRIC FENCE	
										207	70000	50	EACH	STRAW OR HAY BALES	
										601	21100	535	SQ YD	SLOPE PROTECTION, MISC.: GROUT FILLED FABRIC MATS	SEE SHEET 28
										659	10000	3288	SQ YD	SEEDING AND MULCHING	
										659	14000	164	SQ YD	REPAIR SEEDING AND MULCHING	
										659	20000	0.18	TON	COMMERCIAL FERTILIZER	
										659	35000	9	M GAL	WATER	
										660	20000	39	SQ YD	SODDING REINFORCED	
					39					838	20750	8	CU YD	GABIONS WITH ADDITIONAL COATING	
					8					DRAINAGE					
										605	31100	220	LIN FT	AGGREGATE DRAIN	
										PAVEMENT					
										254	01000	267	SQ YD	PAVEMENT PLANING, BITUMINOUS	
										301	46000	373	CU YD	BITUMINOUS AGGREGATE BASE, PG64-22	
										304	20000	331	CU YD	AGGREGATE BASE	
										407	10000	141	GALLON	TACK COAT	
										407	14000	94	GALLON	TACK COAT FOR INTERMEDIATE COURSE	
										408	10000	672	GALLON	BITUMINOUS PRIME COAT	
										448	46050	91	CU YD	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG64-22	
										448	46060	35	CU YD	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 1, PG64-22 (UNDER GUARDRAIL)	
										448	47020	65	CU YD	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG64-22	
										609	26000	25	LIN FT	CURB, TYPE 6	
					25					611	25001	247	SQ YD	REINFORCED CONCRETE APPROACH SLAB (T=15'), AS PER PLAN	SEE SHEET 5
247										TRAFFIC CONTROL					
										626	00300	40	EACH	BARRIER REFLECTOR, TYPE A2	
										626	00400	26	EACH	BARRIER REFLECTOR, TYPE B2	
										642	00102	0.33	MILE	EDGE LINE, TYPE 2	
					0.33					642	00302	0.12	MILE	CENTER LINE, TYPE 2	
					0.12					MAINTENANCE OF TRAFFIC					
										FOR ESTIMATED QUANTITIES, SEE SHEET NO. 9					
										STRUCTURE NO. LAK-90-2687					
										FOR ESTIMATED QUANTITIES, SEE STRUCTURAL PLAN, SHEET 33.					
										614	11000	LUMP		MAINTAINING TRAFFIC	
										623	10000	LUMP		CONSTRUCTION LAYOUT STAKES	
										624	10000	LUMP		MOBILIZATION	
										806	16010	12	MONTH	FIELD OFFICE, TYPE B	
										806	26000	12	MONTH	COMPUTER EQUIPMENT FOR FIELD OFFICE	

CALCULATED
 APC
 CHECKED
 GA

 GENERAL SUMMARY

 LAK-90-26.87
 16
 54