

Filename: K:\VOLI\0007\0290\STRUCT\120350PS
 Date: 05/04/96 Page: 04-13-96 (1447)

REF. NO.	PLAN & PROFILE SHEET NO.	STATION		SIDE	202	202		606	606	606		609		642	642	626		660	838		605			
		FROM	TO		APPROACH SLAB REMOVED	GUARDRAIL REMOVED	GUARDRAIL TYPE 5	ANCHOR ASSEMBLY TYPE B	BRIDGE TERMINAL ASSEMBLY TYPE 1	CURB TYPE 6	EDGE LINE TYPE 2	CENTER LINE TYPE 2	BARRIER REFLECTOR TYPE A2	REINFORCED SODDING	GABIONS WITH ADDITIONAL COATING	AGGREGATE DRAIN	SQ. YD.	CU. YD.	LIN. FT.					
RA-1	18	28+02.96	28+27.96	-	89																			
RA-2	19	31+27.90	31+52.90	-	89																			
RG-1	18	25+68	28+22	LT.		254																		
RG-2	18	26+98	28+38	RT.		140																		
RG-3	19	31+21	33+08	LT.		187																		
RG-4	19	31+35	33+99	RT.		264																		
GR-1	18	25+68	28+05.34	LT.			225	1	1							10								
GR-2	18	25+90	28+26.52	RT.			225	1	1							10								
GR-3	19	31+29.34	33+66	LT.			225	1	1							10								
GR-4	19	31+50.52	33+88	RT.			225	1	1							10								
C-1	19	31+44	31+55	LT.							11													
C-2	19	31+62	31+76	RT.							14													
EL-1	18,19	25+37	34+10	LT.									0.17											
EL-2	18,19	25+64	34+13	RT.									0.16											
CL-1	18,19	27+00	33+25	CL										0.12										
EC-1	19	31+54	31+64	LT.													17	4						
EC-2	19	31+75	31+85	RT.													22	4						
	18	25+90	-	LT.																	12			
	18	26+15	-	RT.																	14			
	18	26+40	-	LT.																	12			
	18	26+65	-	RT.																	14			
	18	26+90	-	LT.																	12			
	18	27+15	-	RT.																	14			
	18	27+40	-	LT.																	12			
	18	27+65	-	RT.																	6			
	18	27+90	-	LT.																	6			
	18	28+15	-	RT.																	7			
	19	31+40	-	LT.																	7			
	19	31+65	-	RT.																	6			
	19	31+90	-	LT.																	6			
	19	32+15	-	RT.																	14			
	19	32+40	-	LT.																	12			
	19	32+65	-	RT.																	14			
	19	32+90	-	LT.																	12			
	19	33+15	-	RT.																	14			
	19	33+40	-	LT.																	12			
	19	33+65	-	RT.																	14			
TOTALS CARRIED TO GENERAL SUMMARY					178	845		900	4	4		25		0.33	0.12	40		39	8		220			

CALCULATED APG CHECKED GA
 ESTIMATED QUANTITIES FROM BEGINNING PROJECT TO END PROJECT
 LAK-90-26.87
 20
 54