

COMPUTATIONS AND SUB-SUMMARY

REF. SHEET NO.	SHEET NO.	LOCATION	STATION TO STATION	202	202	202	202	202	202
				CURB REMOVED	GUARDRAIL REMOVED	WALK REMOVED	STEPS REMOVED	CATCH BASIN OR INLET ABANDONED	CONCRETE TRAFFIC ISLAND REMOVED
				LN.FT.	LN.FT.	SQ.FT.	LUMP	EACH	SO.YDS.
R-4	6	RAMP A	4+57.73 TO 5+47.73	206					
R-3	7	REST AREA	76+07.65 TO 80+99.46	1861					
R-24	7	RAMP B	1+58.64 TO 8+50.90	692					
R-22	8	RAMP C	10+17.73 TO 11+17.73	206					
R-1	8	REST AREA	90+58.19 TO 96+50.00	1861					
R-20	7	RAMP D	2+44.68 TO 9+36.79	692					
R-21	7	RAMP B	0+25.00 TO 1+50.00		125				
R-17	8	RAMP C	11+75.00 TO 15+75.00		400				
R-28	7	RAMP D	0+25.00 TO 5+25.00		500				
R-5	7	REST AREA	76+75.00 TO 80+59.00			1920			
R-10	7	REST AREA	77+50.00			150	LUMP		
R-14	7	REST AREA	79+65.00			580	LUMP		
R-2	8	REST AREA	90+98.65 TO 94+82.65			1920			
R-7	8	REST AREA	92+12.65			580	LUMP		
R-12	8	REST AREA	93+62.65			150	LUMP		
R-4	7	REST AREA	76+30.00						
R-6	7	REST AREA	76+87.00						
R-17	7	REST AREA	80+19.00						
R-19	7	REST AREA	80+75.00						
R-27	7	REST AREA	85+10.00						
R-3	8	REST AREA	90+98.65						
R-5	8	REST AREA	91+38.65						
R-10	8	REST AREA	92+79.82						
R-5	6	E.B.	70+89.88 TO 71+29.88						35.5
R-21	8	W.B.	100+91.84 TO 101+31.84						35.5
TOTAL				5518	1025	5300	LUMP	8	71

REF. SHEET NO.	SHEET NO.	STATION	SIDE	OFFSET (FT.)	202		
					LIGHT POLE AND LUMINAIRE REMOVED	LIGHT POLE FOUNDATION REMOVED 3'X4'	
				LT.	RT.	EACH	EACH
R-1	6	65+54	E.B.	85			
R-2	6	67+70	E.B.	100			
R-3	6	70+09	E.B.	115			
R-6	6	72+40	W.B.	89			
R-7	6	72+46	E.B.	142			
R-1	7	74+76	W.B.	96			
R-2	7	74+83	E.B.	183			
R-7	7	77+10	E.B.	207			
R-8	7	77+10	E.B.	355			
R-9	7	77+45	W.B.	95			
R-11	7	78+50	E.B.	207			
R-12	7	78+50	E.B.	355			
R-13	7	79+70	W.B.	100			
R-15	7	79+90	E.B.	207			
R-16	7	79+90	E.B.	355			
R-18	7	80+75	E.B.	355			
R-22	7	82+00	W.B.	108			
R-23	7	82+45	E.B.	155			
R-25	7	84+60	W.B.	115			
R-26	7	84+90	E.B.	120			
R-29	7	86+85	W.B.	130			
R-30	7	87+40	E.B.	110			
R-31	7	89+90	E.B.	105			
R-4	8	91+40	W.B.	355			
R-6	8	91+65	W.B.	226			
R-8	8	92+40	E.B.	100			
R-9	8	92+55	W.B.	355			
R-11	8	93+17	W.B.	226			
R-13	8	93+75	W.B.	355			
R-14	8	94+45	W.B.	226			
R-15	8	94+90	E.B.	95			
R-16	8	94+96	W.B.	355			
R-18	8	97+50	W.B.	185			
R-19	8	99+87	E.B.	85			
R-20	8	99+90	W.B.	124			
R-23	8	102+40	W.B.	110			
R-24	8	104+90	W.B.	95			
TOTAL						14	37

SHEET NO.	LOCATION	STATION TO STATION	PAVEMENT WIDTH	202	
				LN.FT.	SQ.YD.
6	I-90	66+15.48 - 66+32.15	VAR.		1.9
6	RAMP A	0+00 - 2+00	2 - 11		130.0
6	RAMP A	2+00 - 4+00	11 - 22		359.5
6	RAMP A	4+00 - 6+00	VAR.		487.3
6-7	RAMP A	6+00 - 8+00	16		355.6
7	RAMP A	8+00 - 9+83.60	16		326.4
7	REST AREA	76+7.65 - 78+00	VAR.		1519.7
7	REST AREA	78+00 - 80+00	36 - 40		1688.9
7	REST AREA	80+00 - 80+99.46	VAR.		545.1
7	RAMP B	0+00 - 2+00	16		355.6
7	RAMP B	2+00 - 4+00	16		355.6
7	RAMP B	4+00 - 6+00	16		354.7
7	RAMP B	6+00 - 8+00	14 - 16		333.5
7-8	RAMP B	8+00 - 10+00	VAR.		287.4
8	RAMP B	10+00 - 12+00	7 - 11		200.4
8	RAMP B	12+00 - 14+00	3 - 7		111.6
8	RAMP B	14+00 - 16+33.45	VAR.		38.9
8	I-90	105+49.57 - 106+16.67	VAR.		7.5
8	RAMP C	6+00 - 8+00	2 - 14		180.1
8	RAMP C	8+00 - 10+00	14 - 26		444.2
8	RAMP C	10+00 - 12+00	VAR.		409.9
8	RAMP C	12+00 - 14+00	16		355.6
8	RAMP C	14+00 - 16+00	16		355.6
8	RAMP C	16+00 - 16+09.41	16		16.7
8	REST AREA	90+58.19 - 92+50.54	VAR.		1389.5
8	REST AREA	92+50.54 - 94+50.54	36 - 40		1688.9
8	REST AREA	94+50.54 - 95+50	VAR.		675.2
7-8	RAMP D	0+00 - 2+00	16		355.6
7	RAMP D	2+00 - 4+00	16		355.6
7	RAMP D	4+00 - 6+00	16		355.6
7	RAMP D	6+00 - 8+00	15 - 16		345.7
7	RAMP D	8+00 - 10+00	13 - 15		313.6
7	RAMP D	10+00 - 12+00	9 - 13		238.7
7	RAMP D	12+00 - 14+00	5 - 9		149.8
7	RAMP D	14+00 - 16+00	2 - 5		60.9
6-7	RAMP D	16+00 - 17+19.29	VAR.		13.3
TOTAL					15164.1

SHEET NO.	SIDE	STATION TO STATION	605
			6" SHALLOW PIPE UNDERDRAINS
			LN.FT.
6	E.B.	65+82 TO 71+00	518.0
7-8	E.B.	85+00 TO 96+28.5	1133.5
7	W.B.	74+44 TO 86+00	1158.5
8	W.B.	100+19 TO 106+50	633.5
TOTAL			3443.5

SHEET NO.	203	203	659			
	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	EMBANKMENT	SEEDING AND MULCHING			
				CU.YD.	CU.YD.	SQ.YD.
11	249	569	1716			
12	117	690	1757			
13	39	2090	4584			
14	431	1035	3101			
15	309	421	1256			
16	283	360	1091			
17	446	995	3020			
18	65	2206	3562			
19	65	1875	3140			
20	310	742	2207			
TOTAL				2314	10983	25434

ITEM 202 - CONCRETE SLAB REMOVED					
SHEET NO.	LOCATION	STATION	OFFSET FT.	DESCRIPTION	QUANTITY S.Y.
7	E.B.			PICNIC TABLE 7'X8'	124.4
7	E.B.	78+77	272 RT.	BULLETIN BOARD 20'X10'	22.2
7	E.B.	79+30	267 RT.	TELEPHONE BOOTH 10'X8'	8.9
8	W.B.			PICNIC TABLE 7'X8'	112.0
8	W.B.	92+95	282 LT.	BULLETIN BOARD 15'X10'	16.7
8	W.B.	93+30	282 LT.	TELEPHONE BOOTH 10'X8'	8.9
TOTAL					293.1