

I. Roof Vents

1. Contractor shall install gravity roof ventilators in top of building to provide net free area of 1/150th of net floor area.
2. Roof vents shall be plastic or aluminum.
3. Vents shall be attached directly to the roof sheathing in a manner such that there will be no leakage into the building.

J. Finishes

1. Surfaces to be primed, shall be dry, sanded smooth and have all dust and dirt removed.
2. Stain selected for the building shall be top quality vinyl acrylic laytex or oil base stain.

K. Building Ground

When noted on the site plan, contractor shall provide and install a lightening rod system to the top of the building. System shall include 5/8" diameter x 10' - 0" copperweld ground rods, 5/8" x 24" solid copper air terminals, 17 gauge copper conductors, all rod and wire clamps and bus terminal connectors. System shall be installed in accordance with manufacturer's and all governmental guidelines. Information pertaining to system shall be submitted with bid.

—END—