TRAFFIC CONTROL GENERAL SUMMARY

LAKE COUNTY LAK-90-6.71	OHIO FHWA REGION 5	126 / 182

ITEM	SHEET NUMBERS 124 I	127 I	127 II	128 I	129 I	130 I	131 I	132 I	133 I	154 I	PARTICIPATION I	PARTICIPATION II	PARTICIPATION III	ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	AS PER PLAN SHT. REF.
																		TRAFFIC CONTROL	
633										2	2			633	99000	2	EACH	CONTROLLER ITEM, MISC: CABINET, WITHOUT CONTROLLER, PREWIRED, PEDESTAL MOUNTING, TYPE G, AS PER PLAN	154
644		18.67	5.35	1.46							20.19	5.35		644	00100	25.54	MILE	EDGE LINE	
644		12.80	5.19	0.06							12.86	5.19		644	00200	18.05	MILE	LANE LINE	
644		3580		1701							5281			644	00400	5281	LIN. FT.	CHANNELIZING LINE	
644				79							79			644	00500	79	LIN. FT.	STOP LINE	
644				88							88			644	00600	88	LIN. FT.	CROSSWALK LINE	
644		1177									1177			644	00700	1177	LIN. FT.	TRANSVERSE LINE	
644				9							9			644	01300	9	EACH	LANE ARROW	
644				3							3			644	01400	3	EACH	WORD ON PAVEMENT, 72"	
644		1520									1520			644	30000	1520	LIN. FT.	REMOVAL OF PAVEMENT MARKING	
802	1800										1800			802	00100	1800	EACH	BARRIER REFLECTOR, TYPE A	
802	150										150			802	00200	150	EACH	BARRIER REFLECTOR, TYPE B	
SPEC.	6										6			SPEC.	63009100	6	EACH	SURFACE PREPARATION, EXISTING SUPPORT SECTION	
SPEC.	18										18			SPEC.	630 09102	18	EACH	SURFACE PREPARATION, NEW SUPPORT SECTION	
SPEC.	24										24			SPEC.	630 09104	24	EACH	COATING, EPOXY PRIME COAT, SUPPORT SECTION	
SPEC.	24										24			SPEC.	630 09106	24	EACH	COATING, EPOXY INTERMEDIATE COAT, SUPPORT SECTION	
SPEC.	24										24			SPEC.	630 09108	24	EACH	COATING, URETHANE TOP COAT, SUPPORT SECTION	
632										6	6			632	27300	6	EACH	PIEZOCABLE CLASS II, AXLE SENSOR	

T:\DGN\LAK-90\TRAFFCON\5774TGB.DGN