GENERAL SUMMARY

CALC. BY [illegible] DATE 10-28-22
CHKD. BY DJW DATE 10-28-22

LAKE COUNTY
LAK-90-8.77/29.20

OHIO
FHWA REGION 5

9
101

SHEET NUMBER																				PARTICIPATION			ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION
												2	7	8	76	77	78		101								
																											— ROADWAY —
													4685										202		4685	SQ. YD.	WEARING COURSE REMOVED
													980										202		980	LIN. FT.	GUARDRAIL REMOVED
													LUMP										202		LUMP		EXISTING HEADWALL REMOVED
													1125										606		1125	LIN. FT.	GUARDRAIL, TYPE 5
													27										606		27	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE A
													8										606		8	EACH	BRIDGE TERMINAL ASSEMBLY, TYPE F
													6										606		6	EACH	ANCHOR ASSEMBLY, TYPE A
													2										606		2	EACH	ANCHOR ASSEMBLY, TYPE T
														12223									202		12223	SQ. YD.	WEARING COURSE REMOVED AS PER PLAN (SEE NOTE ON SHEET 2/101)
																											— EROSION CONTROL —
													557										601		557	SQ. YD.	CRUSHED AGGREGATE SLOPE PROTECTION, AS PER PLAN (NOTE ON SHT. 2/101)
													9										601		9	CU. YD.	ROCK CHANNEL PROTECTION, TYPE B W/FABRIC FILTER
																											— DRAINAGE —
													440										605		440	LIN. FT.	AGGREGATE DRAINS
																											— PAVEMENT —
													212										404		212	CU. YD.	ASPHALT CONCRETE, AC-20
													509										407		509	GAL.	TACK COAT
													562										611		562	SQ. YD.	REINFORCED CONCRETE APPROACH SLAB, AS PER PLAN (T=15")
													106										611		106	SQ. YD.	REINFORCED CONCRETE APPROACH SLAB, PARTIAL REPLACEMENT, AS PER PLAN (T=14") (SEE NOTE ON SHEET 2/101)
													546										SPEC.		546	LIN. FT.	PRESSURE RELIEF JOINT, TYPE C
																											— MAINTENANCE OF TRAFFIC —
																11.73							614		11.73	MILE	TEMPORARY EDGE LINES, CLASS I, 947.03, TYPE B
																1.70							614		1.70	MILE	TEMPORARY LANE LINES, CLASS I, 947.03, TYPE B
																0.06							614		0.06	MILE	TEMPORARY CENTER LINES, CLASS I, 947.03, TYPE C
																11,450							614		11,450	LIN. FT.	TEMPORARY CHANNELIZING LINES, CLASS I, 947.03, TYPE B
																230							614		230	LIN. FT.	TEMPORARY DOTTED LINES, 4 INCH, CLASS I, 947.03, TYPE B
																72							614		72	LIN. FT.	TEMPORARY STOP LINES, CLASS I, 947.03, TYPE C
																		4.77					614		4.77	MILE	TEMPORARY EDGE LINES, CLASS I, PAINT
																		4.57					614		4.57	MILE	TEMPORARY LANE LINES, CLASS II, PAINT
																		0.57					614		0.57	MILE	TEMPORARY CENTER LINES, CLASS II, PAINT
																		420					614		420	LIN. FT.	TEMPORARY CHANNELIZING LINES, CLASS I, PAINT
																		100					614		100	LIN. FT.	TEMPORARY TRANSVERSE LINES, CLASS I, PAINT
																		55					614		55	LIN. FT.	TEMPORARY STOP LINES, CLASS I, PAINT
												250											404		250	CU. YD.	BITUMINOUS CONCRETE FOR MAINTAINING TRAFFIC
																	2983						615		2983	SQ. YD.	TEMPORARY PAVEMENT, CLASS A, AS PER PLAN
																3340							622		3340	LIN. FT.	TEMPORARY CONCRETE BARRIER
																3830							622		3830	LIN. FT.	TEMPORARY CONCRETE BARRIER, AS PER PLAN
																6300							622		6300	LIN. FT.	TEMPORARY CONCRETE BARRIER, BRIDGE MOUNTED, AS PER PLAN
															500								SPEC.		500	SQ. FT.	REPLACEMENT SIGNS
															500								SPEC.		500	EACH	REPLACEMENT DRUMS

LAK-90-8.77/29.20