

MAINTENANCE OF TRAFFIC NOTES

FLASHING ARROW PANELS

THE FLASHING ARROW PANELS SHALL BE TYPE C UNLESS OTHERWISE NOTED ON THE MAINTENANCE OF TRAFFIC PLANS. ALL PANELS SHALL CONFORM TO STANDARD CONSTRUCTION DRAWING TC-35.10.

DRUMS

DRUMS SHALL BE LOCATED ON THE MAINTENANCE OF TRAFFIC PLANS. ALL COST FOR INSTALLING, MAINTAINING AND SUBSEQUENT REMOVAL OF SAID DRUMS SHALL BE INCLUDED IN THE LUMP SUM BID PRICE FOR ITEM 614-MAINTAINING TRAFFIC.

WORK ZONE PAVEMENT MARKINGS

PAVEMENT MARKINGS SHALL BE OF THE TYPE AND LOCATION AS SHOWN ON THE MAINTENANCE OF TRAFFIC PLANS, AND SHALL BE IN ACCORDANCE WITH STANDARD DRAWING MT-99.10, 11-14-86.

REPLACEMENT SIGNS

FLAT SHEET SIGNS FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENT OF THE PLANS, SPECIFICATIONS AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASON BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER.

PAYMENT FOR THE NEW SIGNS SHALL BE MADE AT THE PRICE BID PER SQUARE FOOT FOR ITEM SPECIAL REPLACEMENT SIGNS AND SHALL INCLUDE THE COST OF REMOVING AND DISPOSING OF THE DAMAGED SIGNS, HARDWARE AND SUPPORTS, AND PROVIDING NECESSARY REPLACEMENT HARDWARE SUPPORTS, ETC. REPLACEMENT SIGNS SHALL BE NEW BUT OTHER MATERIALS MAY BE USED, SUBJECT TO APPROVAL BY THE ENGINEER.

AN ESTIMATED QUANTITY OF ITEM SPECIAL, REPLACEMENT SIGNS HAS BEEN CARRIED TO THE GENERAL SUMMARY:

ITEM SPECIAL-500 S.F.-REPLACEMENT SIGNS

REPLACEMENT DRUMS

DRUMS FURNISHED BY THE CONTRACTOR IN ACCORDANCE WITH THE REQUIREMENT OF PLANS, SPECIFICATION AND PROPOSAL WHICH BECOME DAMAGED BY TRAFFIC FOR REASONS BEYOND THE CONTROL OF THE CONTRACTOR SHALL BE REPLACED IN KIND WHEN ORDERED BY THE ENGINEER AND PAID FOR UNDER ITEM SPECIAL-REPLACEMENT DRUMS. PAYMENT FOR EACH DRUM SHALL INCLUDE (1) THE COST OF REMOVING AND DISPOSING THE DAMAGED DRUM AND (2) PROVIDING, MAINTAINING AND REMOVING NEW DRUMS IN ACCORDANCE WITH THE CONTRACT REQUIREMENTS FOR THE ORIGINAL DRUM. (REPLACEMENT LIGHTS SHALL NOT BE PAID FOR SEPARATELY BUT CONSIDERED INCIDENTAL TO THIS ITEM OR ITEM 614-MAINTAINING TRAFFIC.) AN ESTIMATED QUANTITY OF ITEM SPECIAL-REPLACEMENT DRUMS HAS BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM SPECIAL-500 E.A.- REPLACEMENT DRUMS

LAW ENFORCEMENT OFFICER WITH PATROL CAR

THE CONTRACTOR SHALL PROVIDE AND PAY ALL COST FOR THE SERVICES OF LAW ENFORCEMENT OFFICER WITH PATROL CAR FOR THE EXCLUSIVE PURPOSE OF CONTROLLING TRAFFIC WHENEVER A CHANGE IN THE TRAFFIC PATTERN TAKES PLACE. THE NUMBER OF OFFICERS AND CARS REQUIRED FOR THIS PURPOSE SHALL BE DETERMINED BY THE CONTRACTOR AND APPROVED BY THE ENGINEER. THE OFFICERS SHALL MOVE THEIR PATROL CARS AS NECESSARY TO INSURE THEIR CONSTANT PRESENCE AT THE POINT(S) OF SLOWDOWN, STOPPAGE OR BACK-UP. PAYMENT FOR THE ABOVE WILL BE INCLUDED IN THE UNIT PRICE BID FOR ITEM SPECIAL-LAW ENFORCEMENT OFFICER WITH PATROL CAR.

IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO MAKE ARRANGEMENTS REGARDING SCHEDULING AND PAYMENT OF LAW ENFORCEMENT OFFICER WITH PATROL CAR. THE FOLLOWING ESTIMATED QUANTITY HAS BEEN CARRIED TO THE GENERAL SUMMARY.

ITEM SPECIAL-LAW ENFORCEMENT OFFICER WITH PATROL CAR....500 HRS.

TEMPORARY PRECAST CONCRETE BARRIER

TEMPORARY PRECAST CONCRETE BARRIER SECTIONS (10 FEET LONG) NECESSARY TO PERFORM THIS ITEM OF WORK SHALL BE SUPPLIED BY THE CONTRACTOR. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL LOADING, UNLOADING AND TRANSPORTATION OF THE BARRIER.

THE BARRIER SECTIONS TO BE LOCATED ON THE BRIDGE DECKS DO NOT HAVE TO BE ANCHORED TO THE DECKS, HOWEVER, THEY SHALL BE MODIFIED AND CONNECTED AS PER THE TEMPORARY CONCRETE BARRIER DETAILS, SEE SHEET No. 96.

TYPE C STEADY BURNING WARNING LIGHTS SHALL BE PROVIDED ON ALL TEMPORARY CONCRETE BARRIERS @ 25' C/C SPACING EXCEPT FOR THOSE BARRIER SECTIONS USED TO FORM THE TAPER.

PAYMENT FOR PRECAST BARRIER OFF THE BRIDGE SHALL BE MADE AT THE CONTRACT PRICE FOR ITEM 622, LINEAR FOOT, TEMPORARY CONCRETE BARRIER.

PAYMENT FOR THE PRECAST BARRIER OFF THE BRIDGE WITH TYPE C STEADY BURNING WARNING LIGHTS SHALL BE MADE AT THE CONTRACT PRICE FOR ITEM 622, LINEAR FOOT, TEMPORARY CONCRETE BARRIER, AS PER PLAN.

PAYMENT FOR THE PRECAST BARRIER ON THE BRIDGE WITH TYPE C STEADY BURNING WARNING LIGHTS SHALL BE MADE AT THE CONTRACT PRICE FOR ITEM 622, LINEAR FOOT, TEMPORARY CONCRETE BARRIER, BRIDGE MOUNTED, AS PER PLAN.

TEMPORARY PAVEMENT, CLASS A, AS PER PLAN

THE TEMPORARY PAVEMENT SHALL BE CLASS A, FLEXIBLE PAVEMENT AND SHALL REMAIN IN PLACE TO SERVE AS THE PERMANENT PAVED SHOULDER.

PAYMENT FOR THE TEMPORARY PAVEMENT ACCEPTED IN PLACE WILL BE AT THE CONTRACT PRICE FOR ITEM 615, SQUARE YARD, TEMPORARY PAVEMENT, CLASS A, AS PER PLAN.