

PAVEMENT MARKINGS SUB SUMMARY									
BRIDGE	621								
	STATION		EDGE LINES (WHITE)	EDGE LINES (YELLOW)	LANE LINES	CENTER LINES	CHANNELIZING LINES	TRANSVERSE LINES	STOP LINES
	TO	FROM	MILES			LIN. FT.			
LAK-90-8.77	27+76	31+99				0.08			
LAK-90-10.15	28+06	31+94				0.07			
LAK-90-12.97	26+66	33+28				0.13			
LAK-90-13.70L	306+75	332+05	0.27	0.48	0.48				
LAK-90-13.70R	305+05	330+45	0.27	0.48	0.48				
LAK-90-14.87L	383+80	395+20	0.37	0.18	0.41		420	100	
LAK-90-14.87R	369+55	383+60	0.26	0.17	0.27				
LAK-90-16.41L	455+25	490+65	0.26	0.09	0.59				
LAK-90-16.41R	433+25	468+70	0.26	0.09	0.59				
LAK-90-19.21	27+35	32+70				0.10			55
LAK-90-20.03L	645+60	661+70	0.29	0.10	0.24				
LAK-90-20.03R	624+70	661+80	0.29	0.10	0.70				
LAK-90-21.10L	702+90	736+30	0.22	0.32	0.63				
LAK-90-21.10R	701+50	714+20	0.23	0.04	0.18				
LAK-90-22.10	26+83	33+24				0.12			
LAK-90-29.20	19+22	22+99				0.07			
SUBTOTALS			2.72	2.05					
TOTALS*			4.77	4.57	0.57	420	100	55	

* THESE TOTALS HAVE BEEN TRANSFERRED TO THE GENERAL SUMMARY

614						
TEMPORARY EDGE LINES (WHITE) CLASS I	TEMPORARY EDGE LINES (YELLOW) CLASS I	TEMPORARY LANE LINES CLASS II	TEMPORARY CENTER LINES CLASS II	TEMPORARY CHANNELIZING LINES CLASS I	TEMPORARY TRANSVERSE LINES CLASS I	TEMPORARY STOP LINES CLASS I
MILES			LIN. FT.			
2.72	2.05					
4.77	4.57	0.57	420	100	55	

TRAFFIC CONTROL NOTES

PAVEMENT MARKINGS

THIS WORK SHALL CONSIST OF FURNISHING AND APPLYING PAVEMENT MARKINGS IN ACCORDANCE WITH ITEM 621 OF THE O.D.O.T. SPECIFICATIONS. THESE PAVEMENT MARKINGS SHALL BE APPLIED AT THE SAME LOCATIONS AND IN THE SAME MANNER AS THE PAVEMENT MARKINGS EXISTING PRIOR TO THE BEGINNING OF CONSTRUCTION. LOCATION, TYPE, AND QUANTITIES CAN BE FOUND IN THE PAVEMENT MARKINGS SUB SUMMARY, THIS SHEET.

THESE QUANTITIES HAVE BEEN INCLUDED IN THE GENERAL SUMMARY.

101 602
 12.01-PP-8.77-10.21
 LAK-90-8.77/29.20