

SUMMARY OF DRIVEWAY QUANTITIES

FED. RD. DIVISION	STATE	PROJECT
2	OHIO	

51
146

LAKE COUNTY
LAK-91-(0.00)-(2.38)

SHEET NO.	REF NO.	Q DRIVE STATION	SIDE	(A) ANGLE Q S.R.91	EXIST. DRIVE TYPE	DRIVE WIDTH		LENGTH OF DRIVE	B-19	T-35	E-1		E-12	I-1	I-15
						5" AGGREGATE BASE COURSE	2" ASPHALTIC CONCRETE SURFACE COURSE		EXCAVATION	EMBANKMENT	PIPE REMOVED 15" & UNDER	12" CLASS F-4 PIPE	WOOD GUARD RAIL POSTS WITHOUT RAIL		
						FT.	FT.	FT.	CU.YDS.	CU.YDS.	CU.YDS.	CU.YDS.	LIN. FT.	LIN. FT.	EACH
VILLAGE OF WILLOUGHBY HILLS	34	1-D	0+00	LT.	90°	SLAG	10	5	31.8	8.4	3.3	11.7			
	34	2-D	4+75	LT.	90°	BITUM.	25	5	10	31.5	12.9	5.2	18.1		
	34	3-D	0+83 TO 0+40	RT.	—	BITUM.	—	—	4	2.7	1.1	3.7			
	34	4-D	0+15	RT.	90°	SLAG	25	5	10	50	16.2	6.5	47.3		
	34	5-D	1+11	RT.	90°	SLAG	25	5	10	79.6	31.4	12.6	175.8	43.2	50
	34	6-D	4+41	RT.	90°	DIRT	12	4	8	61.5	11.9	4.8	47.2		
35	1-D	9+00	LT.	90°	SLAG	20	4	8	17.1	5.8	2.3	8.1			
	2-D	9+30	LT.	90°	SLAG	10	4	8	17.8	3.2	1.3	4.5	18		
	3-D	11+00	LT.	90°	SLAG	8	4	8	65.8	2.5	1.0	29.6	8.1	32	
	4-D	7+91	RT.	90°	GRAVEL	16	4	8	65.2	16.6	6.6	94.3			
	5-D	7+84	LT.	87°	SLAG	11	4	8	31.7	5.9	2.3	8.5			
36	1-D	6+90	RT.	90°	BITUM.	18	4	8	106	38.6	15.4	257.1	10.7	44	
	2-D	7+75	RT.	90°	BITUM.	18	4	8	94	28.9	11.6	238.8	7.2	40	
	3-D	8+47	RT.	71°	BITUM.	18	—	12	69.5	22.9	9.2	105.9	7.8	22	
	4-D	8+93	RT.	86°	BITUM.	VAR. 12 TO 8	4	8	4	1.1	0.4	1.5			
TOTAL									209.0	83.6	1052.1	77.0	40	206	
CITY OF WILLOUGHBY	30	1-D	128+78	RT.	83°	BIT. APRON & GRAVEL DR	13	4	10	26.4	6.5	2.6	11.4	24	
	32	1-D	139+72.5	RT.	69°	SLAG	10	4	12	10.4	2.5	1.0	3.4	14	32
	32	2-D	144+35	RT.	90°	DIRT & GRAVEL	8	4	8	28.9	4.1	1.6	5.7	13	
	37	1-D	3+85	LT.	90°	SLAG	10	4	8	20	3.6	1.5	5.1		
	37	2-D	6+30.5	LT.	90°	SLAG	15	4	8	105	24.8	9.9	2.0	364.5	10
	37	3-D	9+45	LT.	75°	SLAG	12	—	10	79.7	17.1	6.8	3.1	30.9	16
	37	4-D	11+62	LT.	90°	BITUM.	14	4	8	10	4.1	1.6	5.8		50
	37	5-D	0+26 (HANNA RD)	RT.	—	BITUM.	12	4	8	17	4.8	1.9	6.7		8
	38	1-D	122+93.5	LT.	85°	SLAG	9	4	8	20.5	3.3	1.3	4.7		
	38	2-D	121+59	RT.	90°	BITUM.	12	4	8	20.5	4.3	1.7	11.2		
38	3-D	124+29	RT.	90°	BITUM APRON & SLAG DR	10	4	8	24.6	4.3	1.7	5.2			
TOTAL									79.4	31.6	116.5	435.4	67	82	18