

PLOTTED BY: fkonopka
 PLOTTED FROM: i:\Users\bkruuse\p\d\9864\9864qga.dgn
 PLOT SUBMITTED: 09-OCT-1998 09:07
 09864GGA.DGN

SHEET NUMBER											ITEM	ITEM EXT.	GRAND TOTAL	UNIT	DESCRIPTION	SEE SHEET NO.
11	12	14	19	20	23	24	25	76B								
ROADWAY																
											201	11000	LUMP	CLEARING AND GRUBBING		
						1691					202	23000	1691	SQ. YD.	PAVEMENT REMOVED	
					12608						202	23500	12608	SQ. YD.	WEARING COURSE REMOVED	
						1475					202	30000	1475	SQ. FT.	WALK REMOVED	
	1000										202	32000	1000	LIN. FT.	CURB REMOVED	
							18				202	35100	18	LIN. FT.	PIPE REMOVED, 24" AND UNDER	
200											202	38000	200	LIN. FT.	GUARDRAIL REMOVED	
							1				202	58000	1	EACH	MANHOLE REMOVED	
							1				202	58200	1	EACH	INLET REMOVED	
							2				202	58500	2	EACH	CATCH BASIN ABANDONED	
											202	98000	LUMP	REMOVAL MISC.; REMOVAL OF CONCRETE FLOWER PLANTERS	11	
			40			39				51	203	12000	130	CU. YD.	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	
390											203	60001	390	STATION	LINEAR GRADING, AS PER PLAN A	11
2											203	60001	2	STATION	LINEAR GRADING, AS PER PLAN B	11
					14361	4884					254	01000	119245	SQ. YD.	PAVEMENT PLANING, BITUMINOUS	
					66	197					254	01010	263	SQ. YD.	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE	
2											604	38500	2	EACH	MONUMENT ASSEMBLY	
							20				604	39501	20	EACH	MONUMENT BOX ADJUSTED TO GRADE, AS PER PLAN	13
200											606	13000	200	LIN. FT.	GUARDRAIL, TYPE 5	
						1713					608	10000	1713	SQ. FT.	4" CONCRETE WALK	
						4					608	50000	4	EACH	CURB RAMP, TYPE 1	
						27					608	51000	27	EACH	CURB RAMP, TYPE 2	
						350					608	54000	350	SQ. FT.	CURB RAMP, TYPE 2	
											SPECIAL	69050000	5	EACH	MAIL BOX SUPPORT	11
EROSION CONTROL																
											207	10000	2400	SQ. YD.	TEMPORARY SEEDING AND MULCHING	
		2400									207	30000	200	LIN. FT.	FILTER FABRIC FENCE	
		200									207	70000	120	EACH	STRAW OR HAY BALES	
		120									601	32200	1.7	CU. YD.	ROCK CHANNEL PROTECTION, TYPE C, WITH FILTER	
						1.7					659	10000	20000	SQ. YD.	SEEDING AND MULCHING	
		20000									659	20000	0.50	TON	COMMERCIAL FERTILIZER	
		0.50									659	35000	5.00	M. GAL.	WATER	
		5.00									670	40000	174	SQ. YD.	DITCH EROSION PROTECTION	
									174							

CUYAHOGA COUNTY
 LAKE COUNTY
 CUY/LAK-91-15.42/0.00
 GENERAL SUMMARY
 CALCULATED EMK
 CHECKED ENF
 16
 104