

PLOTTED BY: fkonopka
 PLOTTED FROM: i:\users\bkruse\pid09864\09864gbf.dgn
 09864GBF.DGN
 09-OCT-1998 09:09
 1
 2
 3
 4
 5
 6
 7
 8
 9
 10
 11
 12
 13
 14
 15
 16
 17
 18
 19
 20
 21
 22
 23
 24
 25
 26
 27
 28
 29
 30
 31
 32
 33
 34
 35
 36
 37
 38
 39
 40
 41
 42
 43
 44
 45
 46
 47
 48
 49
 50

* BUTT JOINT MEETING EXISTING CONCRETE PAVEMENT

** BUTT JOINT MEETING EXISTING ASPHALT OVERLAY

ROADWAY	LOCATION		LENGTH	AVE. END WIDTH	SURFACE AREA	202	254	254	407	448	446		
	FROM	TO				WEARING COURSE REMOVED	PAVEMENT PLANING, BITUMINOUS	PAVEMENT PLANING, PORTLAND CEMENT CONCRETE	TACK COAT FOR INTERMEDIATE COURSE (0.05 GAL./S.Y.)	TACK COAT (0.10 GAL./S.Y.)	2" ASPHALT CONCRETE INTER. COURSE, TYPE 2, P664-22	1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE 1H, AS PER PLAN	2" ASPHALT CONCRETE INTER. COURSE, TYPE 2, P664-22
			LIN. FT.	LIN FT	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	GALLON	GALLON	CU. YD.	CU. YD.	CU. YD.
CHARDON RD.	4+95.00 **	5+67.40	72.40	CADD	660.67		660.7		9.9	66.1		37.2	9.7
	6+34.48 **	7+10.00	75.52	CADD	751.77		751.8		10.4	75.2		42.6	10.1
EDDY RD.	3+90.00 **	4+65.88	75.88	CADD	354.02		354.0		7.8	35.4		18.9	7.6
	5+42.75 **	6+38.66	95.91	CADD	529.86		529.9		18.8	53.0		29.2	9.2
GLEN-KYLE LN.	10+28.00 *	10+38.00	10.00	CADD	60.11			30.0		6.0		3.3	
TIMBERLINE DR.	10+28.00 **	10+53.00	25.00	CADD	95.19		95.2		0.6	9.5		5.1	0.6
RAMP C-D	5+30.00	5+38.00	8.00	CADD	103.64		103.6		5.2	10.4		4.3	5.8
	5+38.00 **	5+63.00	25.00	CADD	208.55		208.6		2.7	20.9		11.9	2.6
RAMP B	4+82.00	4+95.00	13.00	CADD	96.12		96.1		4.8	9.6		4.0	5.3
	4+95.00 **	5+20.00	25.00	CADD	129.06		129.1		1.5	12.9		7.4	1.4
RAMP A	20+47.00 **	20+72.00	25.00	CADD	75.00		75.0		0.8	7.5		4.4	0.7
RAMP A (CON.)			25.00	CADD	106.37		106.4		1.4	10.6		6.1	1.3
MAPLEGROVE RD.	4+06.00 **	4+71.00	65.00	CADD	330.42		330.4		5.8	33.0		18.2	5.7
	5+27.00 **	5+92.00	65.00	CADD	303.94		303.9		5.8	30.4		16.6	5.6
RIDGE RD.	119+27.60 **	120+13.95	86.35	CADD	409.84		409.8		6.7	41.0		22.8	6.5
	RIGHT HAND TURN LANE			CADD	88.39		88.4		0.9	8.8		5.1	0.9
	121+02.33 **	121+88.77	86.44	CADD	411.31		411.3		6.8	41.1		22.8	6.6
	RIGHT HAND TURN LANE			CADD	87.63		87.6		1.0	8.8		5.1	0.9
HALLE DR.	9+63.00 *	9+73.00	10.00	CADD	66.72			33.3		6.7		3.7	
COLONIAL BLVD.	9+63.00 *	9+73.00	10.00	CADD	64.89			32.4		6.5		3.6	
ASPENWOOD LN.	10+27.00 *	10+37.00	10.00	CADD	62.22			31.1		6.2		3.5	
OAKTREE DR.	9+63.00 *	9+73.00	10.00	CADD	62.80			31.4		6.3		3.5	
TURTLE TR.	10+27.00 **	10+52.00	25.00	CADD	142.22		142.2		1.7	14.2		7.6	0.9
KAISER CT.	10+27.00 *	10+37.00	10.00	CADD	76.89			38.4		7.7		4.3	
TOTALS							4884.0	196.6	92.6	527.8		291.2	81.4
TOTALS CARRIED TO GENERAL SUMMARY							4884	197	93	528		291	81

DRAWN
 EMK
 REVISIONS
 CHECKED
 ENF

ASPHALT QUANTITIES

CUYAHOGA/LAKE COUNTY
 CUY/LAK-91-15.42/00.00