

PLOTTED BY: fkonopka
 PLOTTED FROM: i:\users\bkkruse\pid09864\09864qbb.dgn
 09864qbb.dgn
 26
 PLOT SUBMITTED: 09-OCT-1998 09:10

DRIVES													
REFERENCE NO.	PLAN SHEET NO.	LOCATION	SIDE	WIDTH	LENGTH	EXIST. DRIVEWAY	202	255	203	301	448	452	452
							PAVEMENT REMOVED	FULL DEPTH PAVEMENT SAWING	EXCAVATION NOT INCLUDING EMBANKMENT CONSTRUCTION	BITUMINOUS AGGREGATE BASE, P664-22	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, P664-22 (DRIVEWAYS)	6" PLAIN CONCRETE PAVEMENT	8" PLAIN CONCRETE PAVEMENT
							SQ. YD.	LIN. FT.	CU. YD.	CU. YD.	CU. YD.	SQ. YD.	SQ. YD.
106DR	39	229+58	RT.	49.0	5.0	ASP.					0.95		
107DR	"	234+94	RT.	56.0	12.0	CON.	74.7						74.7
108DR	40	241+97	RT.	40.0	7.0	CON.	31.3	36.0					31.3
109DR	"	247+15	RT.	18.0	7.0	CON.	14.0					14.0	
110DR	"	248+11	RT.	19.0	5.0	ASP.					0.37		
111DR	"	248+68	RT.	22.0	5.0	ASP.					0.42		
112DR	41	250+07	RT.	20.0	5.0	ASP.					0.39		
113DR	"	252+48	RT.	27.0		CON.	(NO WORK)						
114DR	"	253+23	RT.	19.0	5.0	ASP.					0.37		
115DR	"	254+21	RT.	29.0	5.0	ASP.					0.56		
116DR	"	255+84	RT.	21.0	5.0	ASP.					0.41		
117DR	"	256+33	RT.	31.0	11.0	CON.	37.9					37.9	
118DR	42	259+18	RT.	21.0	10.0	CON.	23.3					23.3	
119DR	"	259+63	RT.	21.0	9.0	CON.	21.0					21.0	
120DR	"	262+62	RT.	28.0	5.0	ASP.					0.54		
121DR	"	264+16	RT.	21.0	5.0	ASP.					0.41		
122DR	"	264+83	RT.	42.0	5.0	ASP.					0.81		
123DR	"	266+21	LT.	69.0	5.0	ASP.					1.33		
124DR	43	269+20	LT.	37.0	7.0	CON.	28.8						28.8
125DR	"	270+12	RT.	19.0	5.0	ASP.					0.37		
126DR	"	271+25	RT.	26.0	5.0	ASP.					0.50		
127DR	"	272+45	RT.	19.0	5.0	ASP.					0.37		
128DR	"	272+85	RT.	18.0	5.0	ASP.					0.34		
129DR	"	273+28	LT.	21.0	5.0	ASP.					0.41		
130DR	"	274+68	LT.	20.0	10.0	CON.	22.2					22.2	
131DR	"	275+16	RT.	20.0	5.0	GRA.		1.5	1.16	0.39			
132DR	"	276+00	RT.	28.0	5.0	ASP.					0.54		
133DR	"	277+83	LT.	22.0	5.0	GRA.		1.7	1.27	0.42			
134DR	44	279+79	LT.	23.0	5.0	ASP.					0.44		
135DR	"	282+06	LT.	20.0	5.0	ASP.					0.39		
136DR	"	283+51	LT.	21.0	5.0	ASP.					0.41		
137DR	"	284+27	LT.	31.0		CON.	(NO WORK)						
138DR	"	285+44	LT.	22.0	5.0	ASP.					0.42		
139DR	"	287+75	LT.	27.0	5.0	ASP.					0.52		
140DR	45	290+66	RT.	86.0	13.0	CON.	124.2						124.2
141DR	"	292+28	LT.	63.0	5.0	CON./ASP.				1.22			
142DR	"	295+98	RT.	42.0	8.0	CON.	37.3					37.3	
143DR	"	296+38	LT.	31.0	8.0	CON.	27.6					27.6	
144DR	"	297+21	RT.	58.0	13.0	CON.	83.8					83.8	
145DR	"	297+34	LT.	27.0	7.0	CON.	21.0					21.0	
146DR	"	297+79	LT.	48.0	7.0	CON.	37.3					37.3	
147DR	46	299+28	RT.	59.0	13.0	CON.	85.2					85.2	
148DR	"	299+37	LT.	57.0	7.0	CON.	44.3					44.3	
SUB-TOTALS(C)							713.9	36.0	3.2	2.43	13.30	454.9	259.0
SUB-TOTALS(A) (FROM SHT 22)							726.2	104.0	16.9	12.70	14.13	347.2	379.0
SUB-TOTALS(B) (FROM SHT 22)							250.5	97.0	19.1	8.39	16.92	58.3	154.6
TOTALS							1690.6	237.0	39.2	23.52	44.35	860.4	792.6
TOTALS (TO GENERAL SUMMARY)							1691	237	39	24	44	860	793

WALK									
REFERENCE NO.	PLAN SHEET NO.	LOCATION	SIDE	202	608				
				WALK REMOVED	4" CONCRETE WALK	CURB RAMP, TYPE 1	CURB RAMP, TYPE 2	CURB RAMP, TYPE 1	CURB RAMP, TYPE 2
				SQ. FT.	SQ. FT.	EACH	EACH	SQ. FT.	SQ. FT.
1-CR	26	99+75	LT.		50		1		
2-CR	"	100+30	LT.		50		1		
3-CR	"	100+30	RT.		50		1		
4-CR	27	110+22	LT.		50		1		
5-CR	"	110+67	LT.		50		1		
6-CR	29	127+93	LT.		50		1		
7-CR	"	129+03	LT.		50		1		
8-CR	30	138+75	RT.		50		1		
9-CR	"	139+20	RT.		50		1		
10-CR	"	144+03	RT.		50		1		
11-CR	"	144+46	RT.		50		1		
12-CR	31	152+79	RT.		50		1		
13-CR	"	153+22	RT.		50		1		
14-CR	32	164+01	LT.		75	1			
15-CR	"	164+21	RT.		75	1			
16-CR	"	165+08	LT.		50		1		
16A-CR	"	165+18	LT.		50		1		
16B-CR	"	165+18	RT.		130		3		
17-CR	"	165+65	RT.		50		1		
18-CR	33	171+38	LT.		75	1			
19-CR	"	172+08	RT.		75	1			
20-CR	"	172+37	LT.		50		1		
20A-CR	"	172+82	RT.		183		2		
21-CR	"	173+10	RT.		50		1		
22-CR	35								
23-CR	"								
24-CR	"	194+44	RT.		50		1		
25-CR	"	194+86	RT.		50		1		
26-CR	39	231+35	LT.	50					50
27-CR	42	265+92	LT.	50					50
28-CR	"	266+49	LT.	50					50
31-CR	43	270+82	LT.	50					50
32-CR	"	271+35	LT.	50					50
33-CR	44	286+52	RT.		50		1		
34-CR	"	287+12	RT.		50		1		
35-CR	45	290+39	RT.	50					50
36-CR	"	290+92	RT.	50					50
TOTALS (TO GEN. SUMMARY)				1475	1713	4	27		350

CALCULATED EMK
 CHECKED ENF
 DRIVE AND WALK QUANTITIES
 CUYAHOGA COUNTY
 LAKE COUNTY
 CUY/LAK-91-15.42/0.00
 23
 104