

PLOTTED BY: fkonopka
 PLOTTED FROM: \\users\bkruse\p\d\9864\9864.tna.dgn
 PLOT SUBMITTED: 09-OCT-1998 11:49
 09864TNA.DGN

ITEM 632 - DETECTOR LOOP, AS PER PLAN

THE CONTRACTOR IS CAUTIONED AS TO THE PRESENCE OF EXISTING TRAFFIC SIGNAL LOOP DETECTORS LOCATED IN THE PAVEMENT AT THE STATIONS LISTED BELOW. NEW LOOP DETECTORS SHALL BE PLACED AT THE SAME LOCATIONS AND SAME SIZE AS THE EXISTING LOOP. THE LOOP DETECTOR WIRE SHALL BE REPLACED TO THE EXISTING PULL BOX.

# OF LOOPS	STATION	SIDE	SIZE	# OF TURNS
2	161+39	RT.	6' x 8'	3
2	163+74	LT., RT.	30' x 6'	2-4-2
1	163+86	RT.	18' x 6'	2-4-2
3	165+28	LT., RT.	30' x 6'	2-4-2
2	167+89	LT.	6' x 8'	3
2	208+00	RT.	6' x 6'	3
1	211+74	LT.	6' x 6'	3
1	231+12	LT., RT.	30' x 6'	2-4-2
2	233+08	RT.	6' x 6'	3
2	234+98	LT.	6' x 8'	3
1	237+26	LT., RT.	30' x 6'	2
2	238+50	RT.	6' x 8'	3
1	241+26	LT., RT.	30' x 6'	2
2	241+43	LT.	6' x 6'	3
1	242+46	LT., RT.	30' x 6'	2
2	256+85	LT.	6' x 6'	3
2	294+95	RT.	6' x 6'	3
1	300+03	LT., RT.	30' x 6'	2-4-2
1	300+07	RT.	30' x 6'	2-4-2
1	300+11	RT.	30' x 6'	2-4-2
1	4+19, EDDY RD.	RT.	40' x 6'	2
1	4+22, EDDY RD.	RT.	20' x 6'	2
1	5+67, EDDY RD.	LT.	40' x 6'	2
1	5+86, EDDY RD.	LT.	25' x 6'	2
1	4+81, RAMP B	LT.	35' x 6'	2
1	5+39, RAMP B	LT.	12' x 6'	2
2	4+22, MPLGRV.	LT., RT.	35' x 6'	2
1	5+39, MPLGRV.	LT.	35' x 6'	2-4-2
1	5+44, MPLGRV.	LT.	30' x 6'	2-4-2
1	119+50, RIDGE	RT.	30' x 6'	2
1	119+60, RIDGE	LT., RT.	30' x 6'	2
1	119+68, RIDGE	LT.	6' x 8'	3
2	121+40, RIDGE	LT., RT.	30' x 6'	2

THE UNIT PRICE FOR EACH ITEM 632 - DETECTOR LOOP, AS PER PLAN SHALL INCLUDE ALL LOOP DETECTOR WIRE, CABLE SPLICE KITS IN THE PULL BOX, AS PER SECTION 632.22, SEALANT AND FURNISHING ALL LABOR, TOOLS, MATERIALS AND INCIDENTALS NECESSARY TO COMPLETE THE WORK IN PLACE.

THE FOLLOWING ESTIMATED QUANTITIES HAVE BEEN CARRIED TO THE GENERAL SUMMARY, TO BE USED AS DIRECTED BY THE ENGINEER.

ITEM	DESCRIPTION	QTY.	UNIT
632	DETECTOR LOOP, AS PER PLAN47	EACH

CALCULATED
EMK
CHECKED
ENF

TRAFFIC CONTROL GENERAL NOTES

CUYAHOGA COUNTY
 LAKE COUNTY
 CUY/LAK-91-15.42/0.00