PLOT SUBMITTED: 09-OCT-1998 11:49

PAVEMENT MARKINGS

642

ROADWAY	FROM STATION	TO STATION	DISTANCE	EDGE LINE, TYPE 2 (WHITE)	EDGE LINE, TYPE 2 (YELLOW)	LANE LINE, TYPE 2	CENTERLINE, TYPE 2 DOUBLE/SOLID	CENTERLINE, TYPE 2 BROKEN/SOLID		CHANNELIZING LINE, TYPE 2 (WHITE)		STOP LINE, TYPE 2	CROSSWALK LINE, TYPE 2	TRANSVERSE LINE, TYPE 2 (WHITE)	TRANSVERSE LINE, TYPE 2 (YELLOW)		ISLAND MARKING, TYPE 2	LANE ARROW, TYPE 2	WORD ON PAVEMENT, 72-IN., "ONLY", TYPE 2			
			LIN FT	LIN FT	LIN FT	LIN FT	LIN FT	LIN FT		LIN FT		LIN FT	LIN FT	LIN FT	LIN FT		SQ FT	EACH	EACH			
SR-91	97+00	98+30	130	260			260								65							
	98+30	98+50	20	40			20															
	98+50	99+50	100	200			100			100								2	1			
SR-91	99+50	161+37	6187			12374		12374										24				
	161+37	161+87	50			100	100															
	161+87	162+07	20			40	20															
	162+07	164+02	195			390	195			195								9	2			
	164+02											39										
	164+09												189									
SR-91	165+18									140												
	165+25											39										
	165+25	167+96	271			542	271			271								12	2			
	167+96	168+16	20			40	20															
	168+16	168+66	50			100	100															
	168+66	169+33	134			134		134										2				
	169+33	169+83	50			100	100															
	169+83	170+03	20			40	20															
SR-91	170+03	171+55	152			304	152			152								2	1			
	171+55											52										
	171+62												183									
	172+81											38										
SR-91	172+81	174+55	174			348	174			174								2	1			
	174+55	174+75	20			40	20															
	174+75	175+25	50			100	100															
	175+25	202+85	2760			5520		5520										14				
SR-91	202+85	209+63	678	1356	308	1356											80					
	209+63											25										
	210+80											36										
	210+80	212+51	171	342		342				171								2	1			
	212+51	217+00	449	898		898																
SR-91	217+00	217+87	87	174		261																
	217+87	220+76	289	578		578				289								4	1			
	220+76											37										
	221+72											25										
SR-91	221+72	225+72	400	800		800																
	225+72	226+70	98	98		196		196														
	226+70	227+43	73			146		146		146				73								
	227+43	228+00	57			104		104														
	228+00	228+50	50			100	100															
SR-91	228+50	228+70	20			40	20															
	228+70	231+38	268			536	268			268								4	1			
	231+38											38										
	232+18											34										
	232+25												121									
SR-91	232+25	233+20	95			190	95			95								3	1			
	233+20	233+40	20			40	20															
	233+40	233+90	50			100	100							30								
	233+90	235+93	203			406	406								238							
	235+93											24					40					
TOTALS				4,746	308	26,265	2,661	18,474		2,001		387	493	103	303		120	78	11			
				-0.96 MI		-4.97 MI	-4.00 MI							406 LIN FT								

CALCULATED EMK
CHECKED ENF

TRAFFIC CONTROL QUANTITIES
PAVEMENT MARKINGS

CUYAHOGA COUNTY
LAKE COUNTY
CUY/LAK-91-15.42/0.00

87
104

PLOTTED BY: fkonopka
PLOTTED FROM: i:\users\bkruse\pid09864\09864tsq.dgn
09864TSG.DGN