* BUTT JOINT MEETING EXISTING CONCRETE PAVEMENT ** BUTT JOINT MEETING EXISTING ASPHALT OVERLAY # PAVEMENT TRANSITION

ROADWAY	LOCATION FROM	LOCATION TO	LENGTH	AVE. END WIDTH	SURFACE AREA	202 WEARING COURSE REMOVED	254 PAVEMENT PLANING, BITUMINOUS	254 PAVEMENT PLANING, PORTLAND CEMENT CONCRETE	407 TACK COAT FOR INTERMEDIATE COURSE (0.05 GAL./S.Y.)	407 TACK COAT (0.10 GAL./S.Y.)	448 2" ASPHALT CONCRETE INTER. COURSE, TYPE 2, PG64-22	446 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE 1H, AS PER PLAN	446 2" ASPHALT CONCRETE INTER. COURSE, TYPE 2, PG64-22
			LIN. FT.	LIN FT	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	GALLON	GALLON	CU. YD.	CU. YD.	CU. YD.
S. R. 91	99+00.00 **	99+50.00	50.00	51.50	286.11		286.1		2.8	28.6		12.4	2.1
	99+50.00	160+66.49	6,116.49	56.00	38,058.16		38,058.2		1,902.9	3,805.8		1,585.8	2,114.5
	160+66.49	162+16.49	150.00	62.00	1,033.33		1,033.3		51.7	103.3		43.1	57.4
	162+16.49	174+05.35	1,188.86	68.00	8,982.50		8,982.5		449.1	898.3		374.3	499.1
	174+05.35	175+55.35	150.00	63.00	1,050.00		105.0		52.5	105.0		43.8	58.3
	175+55.35	180+24.66 BK	469.31	58.00	3,024.44		3,024.4		151.2	302.4		126.0	168.0
	180+24.70 FWD	202+84.70	2,260.00	58.00	14,564.44		14,564.4		728.2	1,456.4		606.9	809.1
S. R. 91 LT.	202+84.70	206+42.00	357.30	33.00	1310.10	1310.1			65.5	131.0	72.8	54.6	
S. R. 91 RT.	202+84.70	204+14.00	129.30	31.00	445.37	445.4			22.3	44.5	24.7	18.6	
	204+14.00	206+42.00	228.00	35.00	886.67	886.7			44.4	88.7	49.3	36.9	
S. R. 91	206+42.00	207+35.00	93.00	82.00	847.33	847.3			42.4	84.7	47.1	35.3	
S. R. 91 LT.	207+35.00	207+80.00	45.00	40.00	200.00	200.0			10.0	20.0	11.1	8.3	
	207+80.00	208+25.00	45.00	36.50	182.50	182.5			9.1	18.3	10.1	7.6	
	208+25.00	209+19.02	94.02	33.00	344.74	344.7			17.2	34.5	19.2	14.4	
	209+19.02	209+86.00	66.98	36.00	267.92	267.9			13.4	26.8	14.9	11.2	
S. R. 91 RT.	207+35.00	209+86.00	251.00	35.00	976.11	976.1			48.8	97.6	54.2	40.7	
S. R. 91	209+86.00	210+76.02	90.02	78.00	780.17	780.2			39.0	78.0	43.3	32.5	
S. R. 91 LT.	210+76.02	212+27.53	151.51	40.00	673.38	673.4			33.7	67.3	37.4	28.1	
S. R. 91 RT.	210+76.02	212+27.53	151.51	29.00	488.20	488.2			24.4	48.8	27.1	20.3	
S. R. 91	219+08.09	220+79.52	171.43	73.00	1,390.49	1,390.5			69.5	139.1	77.3	57.9	
	220+79.52	221+42.29	62.77	80.00	557.96	558.0			27.9	55.8	31.0	23.3	
S. R. 91 LT.	221+42.29	224+10.30	268.01	33.00	982.70	982.7			49.1	98.3	54.6	40.9	
S. R. 91 RT.	221+42.29	222+25.46	83.17	37.00	341.92	341.9			17.1	34.2	19.0	14.2	
	222+25.46	224+10.30	184.84	33.00	677.75	677.8			33.9	67.8	37.7	28.2	
S. R. 91	224+10.30	224+66.00	55.70	74.00	457.98	458.0			22.9	45.8	25.4	19.1	
S. R. 91 LT.	224+66.00	225+74.62	108.62	33.00	398.27	398.3			19.9	39.8	22.1	16.6	
S. R. 91 RT.	224+66.00	225+74.62	108.62	33.00	398.27	398.3			19.9	39.8	22.1	16.6	
S. R. 91	225+74.62	226+66.08	91.46	60.50	614.81		614.8		30.7	61.5		25.6	34.2
	226+66.08	231+18.21	452.13	CADD	3,287.00		3,287.0		164.4	328.7		137.0	182.6
	231+18.21	238+50.35	732.14	58.00	4,718.24		4,718.2		235.9	471.8		196.6	262.1
	238+50.35	241+18.00	267.65	57.00	1,695.12		1,695.1		84.8	169.5		70.6	94.2
	241+18.00	297+32.89	5,614.89	56.00	34,937.09		34,937.1		1,746.9	3,493.7		1,455.7	1,941.0
	297+32.89	299+12.89	180.00	62.00	1,240.00		1,240.0		62.0	124.0		51.7	68.9
	299+12.89	299+50.00	37.11	68.00	280.39		280.4		14.0	28.0		11.7	15.6
	299+50.00 #	300+00.00	50.00	68.00	377.78		377.8		4.7	37.8		21.6	4.6
	300+00.00	300+62.21	62.21	68.00	470.03		470.0			47.0		19.6	
WHITE RD.	9+48.00 **	9+73.00	25.00	CADD	130.49		130.5		0.8	13.0		7.0	0.8
METROPARK DR.	10+28.00**	10+53.00	25.00	CADD	160.22		160.2		1.2	16.0		8.6	1.2
PARKVIEW DR.	9+48.00 **	9+73.00	25.00	CADD	101.53		101.5		0.6	10.2		5.5	0.6
ROSEWOOD TR.	9+63.00 *	9+73.00	10.00	CADD	133.11			66.0		13.3		7.4	
STRAWBERRY LN.	10+28.00**	10+53.00	25.00	CADD	100.78		100.8		0.6	10.1		5.4	0.6
MARTIN RD.	10+28.00 **	10+53.00	25.00	CADD	94.94		94.9		0.6	9.5		5.2	0.6
DIXON RD.	10+28.00 **	10+53.00	25.00	CADD	98.74		98.7		0.6	9.9		5.3	0.6
TOTALS						12,608.0	114,360.9	66.0	6,316.6	12,804.6	700.4	5,352.1	6,316.1
TOTALS CARRIED TO GENERAL SUMMARY						12,608	114,361	66	6,317	12,805	700	5,352	6,316

CALCULATED EMK | CHECKED ENF | DRAWN EMK | REVISED

ASPHALT QUANTITIES

CUYAHOGA/LAKE COUNTY
CUY/LAK-91-15.42/00.00

PLOT SUBMITTED: 09-OCT-1998 09:09
09864GBE.DGN
PLOTTED BY: fkonopka
PLOTTED FROM: i:\users\bkruse\pid09864\09864gbe.dgn